

Environmental Services and Water Reclamation
Evelyn Mahieu, Ph. D, Director

P.O. Box 2266 Woodbridge, VA 22195 Telephone 703-335-7932
Fax 703-335-8933

April 14, 2015



Ms. Anna Westernik
Environmental Specialist
Department of Environmental Quality
Northern Virginia Regional Office
13901 Crown Court
Woodbridge, VA 22193

Re: "Prince William County Service Authority Occoquan Forest WTP
– VPA0007 Permit Application"

Dear Ms. Westernik:

Attached is the VPA permit renewal package for the Occoquan Forest Wastewater Treatment Plant – VPA00007. The majority of the data presented is for calendar year 2014.

The Authority is in the process of designing and building a new pump station and sewer to serve the 220 single family homes in the Occoquan Forest subdivision. When complete, the new system will deliver flows from Occoquan Forest to the H.L. Mooney Advanced Water Reclamation Facility. We expect the construction of the pump station to be completed by May 2016.

In the interim, we request that the Department of Environmental Quality administratively continue the Occoquan Forest VPA permit #VPA00007.

If you have any questions or concerns, please feel free to contact me.

Sincerely,



Evelyn Mahieu
Director of Environmental Services and
Water Reclamation

Enclosure

cc: Samer Beidas, PWCSA
Steve Bennett, PWCSA
Maureen O'Shaughnessy, PWCSA
Rachel Carlson, PWCSA

**VIRGINIA POLLUTION ABATEMENT (VPA)
PERMIT APPLICATION**

FORM A – GENERAL INFORMATION

Department of Environmental Quality

Department of Environmental Quality
VIRGINIA POLLUTION ABATEMENT PERMIT APPLICATION
FORM A – GENERAL INFORMATION

INSTRUCTIONS

All applications submitted for a Virginia Pollution Abatement (VPA) Permit shall include this form.

1. FACILITY OR APPLICANT INFORMATION:

- a. If applying for a permit which will authorize management of pollutants at a facility, including but not limited to a wastewater treatment plant, sludge treatment facility, routine storage facility (not located at the treatment plant), or an Animal Feeding Operation (AFO), provide the following information:

- Facility Name: The legal name of the facility managing the pollutants,
- City/County: The city or county in which the facility is located,
- Physical Location/Address: The physical location or address of the facility, and
- Mailing Address: The mailing address of the facility. If the same as physical address write SAME.

- b. If applying for a permit to authorize land application activities only, where no facility is included, provide the following information:

- Applicant Name: The name of the applicant,
- City/County: The city or county in which the land application is proposed,
- Physical Location/Address: The physical address of the office which will manage the activities, and
- Mailing Address: The mailing address of the office which will manage the activities. If the same as physical address write SAME.

2. **OWNER INFORMATION**: Provide the legal name, mailing address, telephone number and e-mail address of the owner or the company making application for the VPA Permit.

3. **OWNER CONTACT INFORMATION**: Provide the name, title, mailing address, telephone number and e-mail address of the individual whom DEQ staff should contact regarding this application. If the owner contact is the same as the owner, write SAME.

4. **EXISTING PERMITS**: List all environmentally-related permits issued to the facility by listing the issuing agency and permit number. Include an existing VPA permit if your facility has one.

5. **NATURE OF BUSINESS**: Provide a general statement of the type of business conducted at the facility. Industrial facilities are requested to provide applicable Standard Industrial Classification (SIC) Codes. SIC Codes may be obtained from Standard Industrial Classification Manual published by the U.S. Department of Labor, Occupational Safety and Health Administration. The manual can be found in public libraries and on the internet.

6. **TYPE OF POLLUTANT MANAGEMENT ACTIVITY**: Indicate pollutants or type of waste(s) handled and whether the facilities are either existing or proposed, or both. Note that the pollutant or type of waste determines which other VPA application forms must be completed. Applicants may also contact the DEQ for assistance.

7. **GENERAL LOCATION MAP**: The purpose of the map is to allow the DEQ staff to readily find the establishment. This map is to show the general location of the establishment. Applicants should use county or United States Geological Survey quadrangle maps. DEQ Regional Offices can provide information for obtaining such maps.

8. **CONSENT TO RECEIVE AND CERTIFY RECEIPT OF ELECTRONIC MAIL**: The Department of Environmental Quality (DEQ) may deliver permits, certifications and plan approvals to recipients, including applicants or permittees, by electronically certified mail where the recipients notify DEQ of their consent to receive mail electronically (§ 10.1-1183). Check only one of the options.

9. **SIGNATURE AND CERTIFICATION STATEMENT**: The application must be signed in accordance with the VPA Permit Regulation (9VAC25-32):

- a. **FOR A CORPORATION**: by a responsible corporate official. For purposes of this section, a responsible corporate official means (1) a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy or decision making functions for the corporation, or (2) the manager of one or more manufacturing, production, or operating facilities employing more than 250 persons or having gross annual sales or expenditures exceeding \$25,000,000 (in second-quarter 1980 dollars), if authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.
- b. **FOR A MUNICIPALITY, STATE, FEDERAL OR OTHER PUBLIC AGENCY**, by either a principal executive officer or ranking elected official. (A principal executive officer of a Federal, Municipal, or State agency includes the chief executive officer of the agency or head executive officer having responsibility for the overall operation of a principal geographic unit of the agency).
- c. **FOR A PARTNERSHIP OR SOLE PROPRIETORSHIP**, by a general partner or the proprietor, respectively.

**VIRGINIA POLLUTION ABATEMENT PERMIT APPLICATION
FORM A
ALL APPLICANTS**

1. FACILITY OR APPLICANT INFORMATION

Facility Name or Applicant Name:	Occoquan Forest Wastewater Treatment Plant
County/City:	Prince William County
Physical Location/ Address:	5901 Davis Ford Road, Manassas, VA 22111
Mailing Address:	P.O. Box 2266, Woodbridge, VA 22195-2266

2. OWNER INFORMATION

Owner Legal Name:	Prince William County Service Authority
Mailing Address:	P.O. Box 2266, Woodbridge, VA 22195-2266
Telephone Number:	703 335 7950
Email address:	bennett@pwcsa.org

3. OWNER CONTACT INFORMATION

Owner Contact Name:	Stephen M. Bennett
Title:	Deputy Director of Water Reclamation
Mailing Address:	P.O. Box 2266, Woodbridge, VA 22195-2266
Telephone Number:	703 393 2062
Email address:	bennett@pwcsa.org

4. EXISTING PERMITS: (e.g., VPA, VPDES; WWP, RCRA; UIC; other)

Agency	Permit Type	Permit Number
VA DEQ	VPA	VPA00007

5. NATURE OF BUSINESS: Domestic Wastewater Treatment

SIC Code(s):	4952	Sewerage System	
--------------	------	-----------------	--

**VIRGINIA POLLUTION ABATEMENT PERMIT APPLICATION
FORM A
ALL APPLICANTS**

6. TYPE OF POLLUTANT MANAGEMENT ACTIVITY: *check the appropriate box(es)*

	<u>Proposed</u>	<u>Existing</u>
<u>Animal Feeding Operations</u> (complete Form B)	<input type="checkbox"/>	<input type="checkbox"/>
<u>Industrial Waste</u> (complete Form C & Form D: Parts D-V & D-VI)	<input type="checkbox"/>	<input type="checkbox"/>
<u>Land Application of Municipal Effluent</u> (complete Form D: Parts D-I & D-III)	<input type="checkbox"/>	<input checked="" type="checkbox"/>
<u>Land Application of Biosolids/Sewage Sludge</u> (complete Form D: Parts D-II, D-IV, D-V & D-VI; and Liability Requirements for Transport, Storage and Land Application of Biosolids Form)	<input type="checkbox"/>	<input type="checkbox"/>
<u>Reclamation and/or Distribution of Reclaimed Wastewater</u> (Application Addendum)	<input type="checkbox"/>	<input type="checkbox"/>

7. GENERAL LOCATION MAP:

Provide a general location map which clearly identifies the location of the facility. **See Attachment 1**


8. CONSENT TO RECEIVE AND CERTIFY RECEIPT OF ELECTRONIC MAIL:

The Department of Environmental Quality (DEQ) may deliver permits, certifications and plan approvals to recipients, including applicants or permittees, by electronically certified mail where the recipients notify DEQ of their consent to receive mail electronically (§ 10.1-1183). Check only one of the following to consent to or decline receipt of electronic mail from DEQ as follows:

- ☒ Applicant or permittee agrees to receive by electronic mail the permit and any plan approvals associated with the permit that may be issued for the proposed pollutant management activity, and to certify receipt of such electronic mail when requested by the DEQ.
- ☐ Applicant or permittee declines to receive by electronic mail the permit and any plan approvals associated with the permit that may be issued for the proposed pollutant management activity.


9. SIGNATURE AND CERTIFICATION STATEMENT:


I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering information, the information submitted is to the best of my knowledge and belief true, accurate and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment for knowing violations. I further certify that I am an authorized signatory as specified in the VPA Permit Regulation (9VAC25-32).

Signature:		Date:	4/14/15
Printed Name:	Dr. Evelyn Mahieu		
Title:	Director of Environmental Services and Water Reclamation		


ATTACHMENT 1

GENERAL LOCATION MAP





Scale 1:15 840



LOCATION MAP

Prince William County Service Authority
Occoquan Forest STP
Land Treatment System



VIRGINIA POLLUTION ABATEMENT APPLICATION

FORM D

MUNICIPAL EFFLUENT AND BIOSOLIDS

PART D-I LAND APPLICATION OF MUNICIPAL EFFLUENT

General Information

1. Facility Name. Name given on Form A. **Occoquan Forest Wastewater Treatment Plant: VPA 00007**
2. Briefly describe the design and provide a line drawing of the wastewater treatment facility which relates the various components of the treatment system including source(s), treatment unit(s) disposal alternatives and flow estimates from the various process units. **Attachment 2**
3. Briefly describe the disposal of any solid or sludge waste materials. **Attachment 2**
4. List all industrial contributors to the wastewater treatment facility. **N/A**
5. Submit a copy of any leasing agreements related to the treatment works and the use or management of the application fields not under direct ownership of the applicant. **N/A**
6. All Privately Owned Treatment Works (PVOTW) designed to serve 50 or more residences must be registered with the State Corporation Commission (SCC) prior to applying for a permit. Provide a copy of the SCC Certificate of Incorporation (for Virginia based operations) or the Certificate of Authority (for out of state operations) with the application. **N/A**

Design Information

Note: This section should be completed for each alternative effluent application system.

Waste Characterization

7. Provide the design flow of the wastewater treatment plant. **Attachment 2**
8. Provide a sewage effluent characterization in accordance with Part D-III of the application. For a proposed facility, estimates based on data obtained from other similar facilities may be used. More than one sample may be required if the effluent may be expected to exhibit diurnal or seasonal variation.
Attachment 3 – Part D Effluent Characterization Form
9. Provide calculations describing the nutrient value of the effluent as mg/l nitrogen (PAN), phosphorus (P_2O_5), potassium (K_2O) and any liming effects which may occur from land application. **Attachment 4 - Nutrients**

Storage and Land Application Requirements **Attachment 5 – Storage and Land Application Requirements**

10. Provide calculations justifying storage and land area requirements for wastewater application including an annual water balance on a monthly basis incorporating such factors as precipitation, evaporation, evapotranspiration, soil hydraulic conductivity, wastewater loading, dry periods, and monthly storage (input and drawdown). Provide daily, weekly and annual hydraulic loading rates (maximum and average).

All facilities must be designed and operated to prevent any discharge to State waters except in the event of a 25 year, 24 hour or greater storm event. DEQ recommends the storage capacity be sufficient to store the entire daily design flow of the treatment works for the duration of the winter months, when land application may be restricted, with a minimum of 60 days storage capacity where adequate climatological data are not available.

11. Provide calculations justifying the land area requirements for land application of sewage effluent taking into consideration average productivity group, crop(s) to be grown and most limiting factor(s), specifically PAN, metal loadings, and Sodium Adsorption Ratio (SAR) or Exchangeable Sodium, where applicable. Demonstrate the most limiting factor for land application on an annual and site life basis.

Site Characterization: Attachment 6

Note: A site characterization is required for each land application site on a field by field basis and for each storage facility. Site booklets organized by Operator/Land Owner and County are preferred.

Divide the land application site into individualized units of fields on the basis of agronomic management practices. For example, soils which are similar for productivity or pH adjustment which are adjacent to each other should be grouped as one field if they can be anticipated to receive effluent on similar schedules. Distinctly different soils which may require different agronomic management should be designated separately. For convenience in meeting permit reporting requirements, keep field units small.

12. Provide a general location map which clearly indicates the location of all the land application sites related to this permit application. (See General Instructions for Map Requirements.)
13. Provide a topographic map of sufficient scale (5 foot contour preferred) clearly showing the location of the following features within 0.25 mile of the site. More than one map may be required if the land application site(s) or treatment/storage facilities are not in close proximity. Provide a legend and approximate scale. Clearly mark field and property boundaries. (See Instructions for map requirements.) **Attachment 6**

- a. Proposed or existing ground water monitoring wells
- b. General direction of ground water movement
- c. Water wells, abandoned or operating
- d. Surface waters
- e. Springs **N/A**
- f. Public water supply(s) **N/A**
- g. Sinkholes **N/A**
- h. Underground and/or surface mines **N/A**
- i. Mine pool (or other) surface water discharge points **N/A**
- j. Mining spoil piles and mine dumps **N/A**
- k. Quarry(s) **N/A**
- l. Sand and gravel pits **N/A**
- m. Gas and oil wells **N/A**
- n. Diversion ditch(s) **N/A**
- o. Agricultural drainage ditch(s) **N/A**
- p. Occupied dwellings, including industrial and commercial establishments **N/A**
- q. Landfills or dumps **N/A**
- r. Other unlined impoundments **N/A**
- s. Septic tanks and drainfields **N/A**
- t. Injection wells **N/A**
- u. Rock outcrops **N/A**

14. For each land application site, provide a site plan, preferably topographically based, of sufficient detail to clearly show any landscape features which require buffer zones or may limit land application. Clearly show the field boundaries, property lines, and the location of any subsurface agricultural drainage tile, as appropriate.

Attachment 6

Provide a site plan legend which identifies the following landscape features:

- a. Drainage ways
- b. Rock outcrops **N/A**
- c. Sink holes **N/A**
- d. Drinking water wells and springs **N/A**
- e. Monitoring wells

- f. Property lines
- g. Roadways **N/A**
- h. Occupied dwellings **N/A**
- i. Slopes (greater than 8% by slope class)
- j. Wet spots **N/A**
- k. Severe erosion **N/A**
- l. Frequently flooded soils (SCS designation) **N/A**
- m. Surface waters

15. Provide a detailed soil survey map, preferably photographically based, with the field boundaries clearly marked. (A USDA-SCS soil survey map should be provided, if available.)

Attachment 7

Provide a detailed legend for each soil survey map which uses accepted USDA-SCS descriptions of the typifying pedon for each soil series (soil type). Complex associations may be described as a range of characteristics. Soil descriptions should include the following information:

- a. Soil symbol
 - b. Soil series, textural phase and slope class
 - c. Depth to seasonal high water table
 - d. Depth to bedrock
 - e. Estimated productivity group (for the proposed crop rotation).
 - f. Estimated infiltration rate (surface soil)
 - g. Estimated permeability of most restrictive subsoil layer
16. Representative soil borings and test pits to a depth of five feet or to bedrock if shallower, are to be coordinated for the typifying pedon of each soil series (soil type). Soil descriptions shall include as a minimum the following information:

Attachment 7

- a. Soil symbol
- b. Soil series, textural phase and slope class
- c. Depth to seasonal high water table
- d. Depth to bedrock
- e. Estimated productivity group (for the proposed crop rotation).
- f. Estimated infiltration rate (surface soil)
- g. Estimated permeability of most restrictive subsoil layer

17. Collect and analyze soil samples for the following parameters for each field, weighted to best represent each of the soil borings performed for Item 16.

Attachment 8

- a. Soil organic matter (%)
- b. Soil pH (std. units)
- c. Cation exchange capacity (meg/100g)
- d. Total nitrogen (ppm)
- e. Organic nitrogen (ppm)
- f. Ammonia nitrogen (ppm)
- g. Nitrate nitrogen (ppm)
- h. Available phosphorus (ppm)
- i. Exchangeable sodium (mg/100g)
- j. Exchangeable calcium (mg/100g)
- k. Copper (ppm)
- l. Nickel (ppm)
- m. Zinc (ppm)
- n. Cadmium (ppm)
- o. Lead (ppm)
- p. Chromium (ppm)
- q. Manganese (ppm)
- r. Particle size analysis or USDA textural estimate (%)
- s. Hydraulic conductivity (in/hr.)

Crop and Site Management

18. Relate the crop nutrient needs to anticipated yields, soil productivity rating and the various fertilizer or nutrient sources from effluent and chemical fertilizers.

Attachment 9

If the effluent may be expected to possess unusual properties, provide a description of any plant tissue testing, supplemental fertilization or intensive agronomic management practices which may be necessary.

19. Using a narrative format and referencing any related charts, describe the proposed cropping system. Show how the crop rotation and management will be coordinated with the design of the land application system. Include any supplemental fertilization program, and the coordination of tillage practices, planting and harvesting schedules and timing of land application.

Attachment 9

ATTACHMENT 2

PART D-1, ITEMS 1 THROUGH 7
GENERAL INFORMATION

OCCOQUAN FOREST WASTEWATER TREATMENT PLANT

PROCESS DESCRIPTION AND OPERATION

The Prince William County Service Authority owns and operates the Occoquan Forest Wastewater Treatment Plant. This wastewater treatment facility is designed to provide service to 220 single family residential homes within the Occoquan Forest subdivision. No industrial or commercial waste is treated.

The attached process flow diagram describes the sequence of treatment. Raw wastewater (sewage) enters an extended aeration activated sludge plant having a capacity of 88,000 GPD (0.088 MGD). The plant consists of two Davco package plants, each with a capacity of 44,000 GPD. Clarified secondary effluent is metered and chlorinated before entering a 4.7 MG holding pond. Holding pond effluent is metered, chlorinated and pumped to a 14.3 acre spray irrigation system for effluent disposal.

Aerobically digested waste activated sludge is hauled to the Neabsco Pump Station or directly to the H.L. Mooney Advanced Water Reclamation Facility where solids are disposed of by incineration. Incinerated ash is hauled to Prince William County Landfill.

The Occoquan Forest Treatment Plant is serviced 7 days per week by operation personnel, one of whom holds a VA Wastewater Operators License.

Liquid Treatment:

Preliminary Treatment (Communitor) —→ Extended Aeration Activated Sludge —→


Secondary Clarification —→ Metering and Chlorination —→


Polishing / Holding Pond —→ Metering and Chlorination —→ Spray Irrigation

Solids Treatment

Waste Activated Sludge —→ Aerobic Digestion —→ Haul to H.L. Mooney AWRF for
Treatment and Incineration

OCCOQUAN FOREST WTP





VIRGINIA POLLUTION ABATEMENT APPLICATION

FORM D

MUNICIPAL EFFLUENT AND BIOSOLIDS

PART D-III EFFLUENT CHARACTERIZATION FORM

1. Facility Name: Occoquan Forest Wastewater Treatment Plant
2. Source or Generator: N/A
3. Type of Treatment: Secondary / Extended Aeration : Spray Irrigation
4. Degree of Treatment: 90%
5. Provide at least one analysis for each parameter listed under effluent. Upon review, additional analyses may be required by DEQ. **CY-2014 Data Attached – 3 pages**

<u>Parameter</u>	<u>Effluent</u>	
BOD ₅	<u>6.6</u>	mg/l
TSS	<u>4.8</u>	mg/l
TRC	<u>4.0</u>	mg/l
Percent Solids	<u>N/A</u>	%
pH	<u>7.4</u>	S.U.
Nitrogen, (Nitrate)	<u>13.5</u>	mg/l
Nitrogen, (Ammonium)	<u>11.9</u>	mg/l
Nitrogen, (Total Kjeldahl)	<u>11.5</u>	mg/l
Phosphorus, (Total)	<u>5.7</u>	mg/l
Potassium, (Total)	<u>12</u>	mg/l
Sodium	<u>103</u>	mg/l

6. Provide at least one analysis of any other pollutants which you believe may be present in the effluent. Upon review, additional analyses may be required by DEQ. **CY-2014 Data Attached – 3 pages**

<u>Parameter</u>	<u>Effluent</u>	
Lead	<u><0.005</u>	mg/l
Cadmium	<u><0.0025</u>	mg/l
Copper	<u><0.05</u>	mg/l
Nickel	<u><0.05</u>	mg/l
Zinc	<u><0.05</u>	mg/l
Other	<u>See Attached</u>	mg/l

VPA MONITORING REPORT - Occoquan Forest WWTP
VPA Permit No. VPA0007

FORM 1 - Page 1 of 3

Wastewater Monitoring
LOCATION: Before Holding Pond

Parameter	Influent Flow to Pond (1)	BOD ₅	TSS	TRC	Fecal Collform	pH	Alkalinity as CaCO ₃	Conductivity
Limit	NL	30 Monthly Average / 60 Maximum	30 Monthly Average / 60 Maximum	(2)	200/100 ml	6.0 - 9.0	NL	NL
Unit	MGD	ppm	ppm	ppm	n/100ml	S.U.	ppm	µmho/cm
Frequency	Continuous	2/Month	2/Month	1/Day	1/Month	1/Day	1/Month	1/Month
Sample Type	Totalizing, Indicating	Grab	Grab	Grab	Grab	Grab	Grab	Grab
Required Reporting	1/Month	1/Month	1/Month	1/Month	1/Month	1/Month	1/Month	1/Month
January	0.095	6.5/10.0	1.6/1.7	5.0	32.0	7.0/7.7	288	869
February	0.091	10.0/11.0	13.7/16.4	6.2	56.0	7.2/7.6	170	704
March	0.131	11.5/15.0	13.1/21.4	5.8	110.0	7.4/7.7	247	921
April	0.222	2.5/3.0	2.0/2.3	3.1	2.0	7.0/7.5	147	624
May	0.081	4.0/5.0	1.7/3.4	2.0	130.0	6.7/7.4	73	762
June	0.032	2.5/3.0	0.8/1.5	4.2	8.0	7.3/7.8	255	944
July	0.040	13.5/23.0	3.6/4.8	4.3	1.8	7.1/7.4	153	957
August	0.045	3.5/4.0	2.9/3.1	3.1	11.0	6.9/7.7	145	857
September	0.032	1.5/3.0	1.4/2.7	3.8	4.0	7.1/7.9	137	853
October	0.028	3.5/4.0	2.3/2.5	3.2	130.0	7.0/8.1	127	815
November	0.073	3.5/4.0	2.7/5.3	5.0	170.0	6.8/7.8	82	852
December	0.061	4.5/7.0	2.3/2.5	2.2	175.0	6.7/7.8	109	786

VPA MONITORING REPORT - Occoquan Forest WWTP
VPA Permit No. VPA0007

FORM 1 - Page 2 of 3

Wastewater Monitoring
LOCATION: Before Holding Pond

Parameter	NH ₃ -N	NO ₃ -N	TKN	Total Phosphorus	Total Potassium	Total Sodium	Total Calcium	Total Magnesium	Sodium Absorption Ratio	Boron (3)
Limit	NL	NL	NL	NL	NL	NL	NL	NL	NL	NL
Unit	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	NA	ppm
Frequency	1/Month	1/Month	1/Month	1/Month	1/Month	1/Month	1/Month	1/Month	1/Month	1/3 Years
Sample Type	Grab	Grab	Grab	Grab	Grab	Grab	Grab	Grab	Calculated	Grab
Required Reporting	1/Month	1/Month	1/Month	1/Month	1/Month	1/Month	1/Month	1/Month	1/Month	1/3 Years
January	30.50	0.57	31.00	5.52	11.10	102.00	40.70	6.20	3.92	NA
February	9.90	0.40	17.00	2.51	6.99	74.20	31.80	4.69	3.25	NA
March	28.50	<0.25	29.60	4.02	11.40	92.90	35.90	6.29	3.74	NA
April	10.90	2.76	12.40	2.03	7.30	73.80	27.00	4.70	3.45	NA
May	5.00	27.40	2.84	4.81	12.60	94.40	35.60	6.33	3.83	NA
June	18.50	0.28	28.40	4.48	12.20	108.00	38.00	6.27	4.38	NA
July	1.23	11.90	3.67	4.56	12.70	153.00	38.60	5.83	6.06	NA
August	1.83	18.10	4.14	6.76	15.20	118.00	38.30	6.41	4.63	NA
September	<0.20	11.60	1.22	6.47	13.30	119.00	34.70	6.01	4.88	NA
October	<0.20	23.10	2.20	6.49	13.90	104.00	38.10	6.29	4.11	0.251
November	<0.20	37.60	2.31	7.58	15.10	105.00	40.50	6.57	4.01	NA
December	0.68	15.10	2.10	13.00	12.80	96.90	41.80	6.56	3.68	NA

VPA MONITORING REPORT - Occoquan Forest WWTP
VPA Permit No. VPA0007

FORM 1 - Page 3 of 3

Wastewater Monitoring

LOCATION: Before Holding Pond

Parameter	Chloride (3)	Molybdenum (3)	Copper (3)	Cobalt (3)	Iron (3)	Manganese (3)	Nickel (3)	Zinc (3)
Limit	NL	NL	NL	NL	NL	NL	NL	NL
Unit	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm
Frequency	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years
Sample Type	Grab	Grab	Grab	Grab	Grab	Grab	Grab	Grab
Required Reporting	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years
October-11	139	<0.05	<0.05	<0.05	0.060	<0.05	<0.05	<0.05
October-12	170	<0.05	<0.05	<0.05	0.068	<0.05	<0.05	<0.05
October-13	142	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05
October-14	91.8	<0.05	<0.05	<0.05	<0.055	<0.05	<0.05	<0.05

- (1) Influent flow to be measured after all treatment and prior to holding pond storage
- (2) No more than three TRC samples taken after the chlorine contact tank and prior to storage shall be less than 1.0 mg/l for any calendar month, and no TRC sample shall be less than 0.6 mg/l.
- (3) Sampling for micronutrients in the wastewater shall be conducted triennially in October in conjunction with soil sampling. If elevated levels of micronutrients are observed during soil sampling, micronutrient sampling should be increased to an annual frequency. Metals are to be reported as total recoverable.

Legend: NL = No Limit (monitoring requirement only)



Analytics Corporation
10329 Stony Run Lane
Ashland, VA 23005
Phone: (804) 365-3000
Fax: (908) 365-3002

ANALYTICAL RESULTS

Workorder: 1025744 OCCOQUAN FOREST FINAL EFFLUENT

Lab ID: 1025744001 Date Received: 03/30/2015 8:37 Matrix Aqueous Liquid
Sample ID: 15032504-31 Date Collected: 03/26/2015 8:00 Sample Type: GRAB

Parameters	Results	Units	Report Lim	DF	Prepared	By	Analyzed	By	Qual	Certifications
Analytical Method: EPA 200.8		Preparation Method: EPA 200.8								
Cadmium	<0.00250	mg/L	0.0025	1	03/31/2015	08:40 JRM	3/31/2015	16:32 HB		V
Lead	<0.00500	mg/L	0.0050	1	03/31/2015	08:40 JRM	3/31/2015	16:32 HB		V

CERTIFICATE OF ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Analytics Corporation



Analytics Corporation
10329 Stony Run Lane
Ashland, VA 23005
Phone: (804) 365-3000
Fax: (908) 365-3002

ANALYTICAL RESULTS

Workorder: 1025744 OCCOQUAN FOREST FINAL EFFLUENT

Qualifiers

--

Certification Index:

V = Virginia (NELAC) - 1 VAC 30-46 H 1, Laboratory ID: 460160, Certificate #: 7668

CERTIFICATE OF ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Analytics Corporation

ATTACHMENT 4

PART D-1, ITEM 9, CALCULATIONS DESCRIBING
NUTRIENT VALUE



Prince William County Service Authority
Occoquan Forest STP

**Summary
Wastewater Nutrients**

2014

Month	TKN	NO ₃ -N	NH ₃ -N	PO ₄	K	Ca	Mg	Na
January	31.00	0.57	30.50	5.52	11.10	40.70	6.20	102.00
February	17.00	0.40	9.90	2.51	6.99	31.80	4.69	74.20
March	29.60	<0.25	28.50	4.02	11.40	35.90	6.29	92.90
April	12.40	2.76	10.90	2.03	7.30	27.00	4.70	73.80
May	2.84	27.40	5.00	4.81	12.60	35.60	6.33	94.40
June	28.40	0.28	18.50	4.48	12.20	36.00	6.27	108.00
July	3.67	11.90	1.23	4.56	12.70	38.60	5.83	153.00
August	4.14	18.10	1.83	6.76	15.20	38.30	6.41	118.00
September	1.22	11.60	<0.20	6.47	13.30	34.70	6.01	119.00
October	2.20	23.10	<0.20	6.49	13.90	38.10	6.29	104.00
November	2.31	37.60	<0.20	7.56	15.10	40.50	6.57	105.00
December	2.10	15.10	0.68	13.00	12.80	41.80	6.56	96.90
Average	11.41	13.53	11.89	5.68	12.05	36.58	6.01	103.43

All values are reported as mg/l



Prince William County Service Authority
Occoquan Forest STP

Summary
Wastewater Nutrient Addition
Nitrogen-Phosphorus-Potassium
Pounds Per Acre Applied

2014

Nutrient	South (Upper) SF 3	Middle SF 2	North (Lower) SF 1
Plant Available Nitrogen (PA-N)	74.09	9.24	80.33
Phosphorus (PO ₄)	35.50	4.41	38.38
Potassium	75.08	9.36	81.41

The PA-N is reported as a total of the monthly additions of PA-N in the wastewater divided by the monthly average percentage of water applied to each spray field. The PA-N is calculated each month using the monthly results of the Nitrogen found in the wastewater.

The phosphorus and potassium totals are calculated using the 2014, twelve (12) month average found on the previous page containing the Wastewater Nutrient Addition Summary.

VPA MONITORING REPORT - Occoquan Forest WWTP
VPA Permit No. VPA0007

FORM 2 - Page 1 of 3

Land Application

LOCATION: Holding Pond/Application Sites

Parameter	No. of Acres Irrigated	Zones Applied (Designate Areas) (1)	Irrigation Rate (2, 3, 4)	Effluent Flow (Effluent Vol. Applied from Storage to Area) (2, 3, 4)	Total Volume Applied to North Branch Irrigation Area (2, 3, 4, 5)
Limit	NA	NA	(4)	NL	NL
Unit	Acres	NA	In/Mon/Acre	Gal/Site/Month	In/Mon/Acre
Frequency	1/Month	1/Month	1/Month	1/Month	1/Month
Sample Type	Measured	Measured	Calculated	Measured	Calculated
Required Reporting	1/Month	1/Month	1/Month	1/Month	1/Month
January	14.3	1, 2, & 3	0.28	107965.00	0.00
February	14.3	1, 2, & 3	0.00	0.00	0.00
March	14.3	1, 2, & 3	1.13	436962.00	2.10
April	14.3	1, 2, & 3	4.34	1685679.00	4.85
May	14.3	1, 2, & 3	2.79	1084073.00	4.55
June	14.3	1, 2, & 3	3.25	1260081.00	3.83
July	14.3	1, 2, & 3	3.59	1394613.00	4.40
August	14.3	1, 2, & 3	1.59	615834.00	0.82
September	14.3	1, 2, & 3	2.29	887486.00	5.10
October	14.3	1, 2, & 3	1.11	432345.00	1.98
November	14.3	1, 2, & 3	0.00	0.00	0.00
December	14.3	1, 2, & 3	1.91	741356.00	2.20

VPA MONITORING REPORT - Occoquan Forest WWTP
VPA Permit No. VPA0007

FORM 2 - Page 2 of 3

Land Application

LOCATION: Holding Pond/Application Sites

Parameter	Total Volume Applied to Middle Branch Irrigation Area (2, 3, 4, 5)	Total Volume Applied to South Branch Irrigation Area (2, 3, 4, 5)	Rainfall (6)	Evapotranspiration Rate (6)	Volume In Storage (7)
Limit	NL	NL	NA	NA	NL
Unit	Inches/Month/Acre	Inches/Month/Acre	Inches/Month	Inches/Month	Million Gallons
Frequency	1/Month	1/Month	1/Day	1/Week	1/Month
Sample Type	Calculated	Calculated	Measured	Estimated	Measured
Required Reporting	1/Month	1/Month	1/Month	1/Month	1/Month
January	0.00	0.74	3.30	0.04	3.68
February	0.00	0.00	4.30	0.10	4.05
March	0.00	0.92	6.30	0.74	4.05
April	0.77	6.25	9.30	2.05	3.03
May	0.00	2.93	5.70	3.70	2.75
June	0.00	4.85	3.20	5.23	1.95
July	1.62	4.13	6.90	6.21	1.33
August	0.00	3.42	6.80	5.59	1.39
September	0.57	0.66	2.90	3.87	1.09
October	0.00	1.01	4.00	2.04	1.63
November	0.00	0.00	3.90	0.81	2.07
December	0.47	2.59	5.80	0.16	2.20

VPA MONITORING REPORT - Occoquan Forest WWTP
VPA Permit No. VPA0007

FORM 2 - Page 3 of 3


Land Application

LOCATION: Holding Pond/Application Sites

Parameter	Lagoon Freeboard	Effluent PAN Applied	Other N Applied (Fertilizer, etc.)	Total PAN Applied YTD	Total Residual Chlorine
Limit	2 Feet Minimum	(8)	(8, 9)	(8)	2.0 mg/l
Unit	Feet	Pounds/Acre/Month	Pounds/Acre/Month	Pounds/Acre	Inches/Month
Frequency	1/Month	1/Month	1/Month	1/Month	1/Day
Sample Type	Measured	Calculated	Measured	Calculated	Measured
Required Reporting	1/Month	1/Month	1/Month	1/Month	1/Month
January	2.42	0.88	0.00	0.88	3.40
February	2.16	0.00	0.00	0.88	0.00
March	2.42	3.93	0.00	4.81	2.70
April	2.67	14.30	0.00	19.10	2.10
May	3.17	5.05	0.00	24.20	2.10
June	4.33	3.22	0.00	27.40	2.20
July	5.08	7.40	0.00	34.80	2.80
August	6.25	2.48	0.00	37.30	2.90
September	6.08	1.78	0.00	39.10	2.70
October	6.08	3.12	0.00	42.20	3.00
November	5.33	0.00	0.00	42.20	0.00
December	4.80	6.36	0.00	48.60	2.80

ATTACHMENT 5

PART D-1, ITEMS 10 AND 11, STORAGE AND LAND
APPLICATION REQUIREMENTS



Occoquan Forest STP

Calculations

Plant Design/Permitted Flow Capacity

88,000 Gallons Per Day (GPD)
36.25 Inches Average Rainfall
37.00 Inches Average Evaporation
14.25 Acres – Total Irrigation Area
13.57 Acres – Effective Spray Area


$365 \text{ Days/Year} \times 88,000 \text{ GPD} = 32,120,000 \text{ Gallons Per Year}$
 $32,120,000 \text{ GPY} \div 27,154 \text{ Gallons Per acre Inch of Water} = 1,182.9 \text{ AI}$

$1,182.9 \text{ Total AI of Water} \div 14.25 \text{ Total Acres} = 83.0 \text{ AI/Year}$
 $1,182.9 \text{ Total AI of Water} \div 13.57 \text{ Spray Acres} = 87.2 \text{ AI/Year}$

$83.0 \text{ AI/Acre} \div 52 \text{ Weeks Per year} = 1.60 \text{ AI/Week of Water}$
 $87.2 \text{ AI/Acre} \div 52 \text{ Weeks Per year} = 1.68 \text{ AI/Week of Water}$

$36.25 \text{ AI/Acre Annual Rainfall} - 102\% \text{ Evaporation} = -0.75 \text{ AI/Acre}$
 $\div 52 \text{ Weeks Per Year} = 0.01 \text{ AI/Week Net Loss of Rain Water}$

$1.68 \text{ AI/Week} + (-0.01) \text{ AI/Week} = 1.67 \text{ AI/Week}$ to operate the Spray System at Design/Permitted Flow (Includes Rain water Addition).



Occoquan Forest STP

Calculations

Plant Average Daily Flow [Last Five (5) Year Average]

42,163 Gallons Per Day (GPD)
36.25 Inches Average Rainfall
37.00 Inches Average Evaporation
14.25 Acres – Total Irrigation Area
13.57 Acres – Effective Spray Area


$365 \text{ Days/Year} \times 42,163 \text{ GPD} = 15,389,426 \text{ Gallons Per Year}$
 $15,389,426 \text{ GPY} \div 27,154 \text{ Gallons Per acre Inch of Water} = 566.7 \text{ AI}$

$566.7 \text{ Total AI of Water} \div 14.25 \text{ Total Acres} = 39.8 \text{ AI/Year}$
 $566.7 \text{ Total AI of Water} \div 13.57 \text{ Spray Acres} = 41.8 \text{ AI/Year}$

$39.8 \text{ AI/Acre} \div 52 \text{ Weeks Per year} = 0.77 \text{ AI/Week of Water}$
 $41.8 \text{ AI/Acre} \div 52 \text{ Weeks Per year} = 0.80 \text{ AI/Week of Water}$

$36.25 \text{ AI/Acre Annual Rainfall} - 102\% \text{ Evaporation} = -0.75 \text{ AI/Acre}$
 $\div 52 \text{ Weeks Per Year} = 0.01 \text{ AI/Week Net Loss of Rain Water}$

$0.80 \text{ AI/Week} + (-0.01) \text{ AI/Week} = 0.79 \text{ AI/Week}$ to operate the Spray
System at Actual Average Flow (Includes Rain water Addition).




Design Flow
Calculations
for the
Storage Facility

- 4,945,600 Gallons Storage Capacity
- 32,120,000 GPY Design Capacity
- Design Capacity = 56.2 Days Storage

If the storage facility were used for the maximum amount of time during inclement weather, then the total gallons (32,120,000) for the year would be sprayed during 308.8 (365-56.2) days of the year rather than the full calendar year of 365 days.

- $32,120,000 \div 308.8 \text{ days} = 104,015 \text{ Gallons/Day Sprayed}$
- $104,015 \text{ GPD} \div 27,154 \text{ Gallons/Acre Inch} = 3.83 \text{ AI/Day}$
- $3.83 \text{ AI/Day} \div 13.57 \text{ Spray Acres} = 0.282 \text{ AI/Acre/Day}$
- $0.282 \text{ AI/Acre/Day} \times 7 \text{ Days/Week} = 1.97 \text{ AI/Week for the spray area}$
- $0.282 \text{ AI/Acre} \times 27,154 \text{ Gallons/Acre Inch} = 7,657 \text{ Gallons/Day/Acre}$

Using the pump operating ranges of 308 GPM to 538 GPM, the spray time needed to apply the 7,657 GPA would range from less than 15 minutes to 25 minutes per day. The most restrictive soil zone has a permeability range of 0.6-6.0 inches per hour. The 0.282 AI of spray water is less than $\frac{1}{2}$ of the water quantity, which the most restrictive layer of soil can handle. Even when the rainwater is added into the calculations, it will not impact the ability of the soil to handle the total amount on a daily basis. By operating each of the three (3) sections of the spray field on a rotation of once every three (3) days at 0.85 AI/Day of spraying (spray one day and rest two days), we have the capacity to spray the actual average flow using the current storage capacity. We will operate the spray system at a rate so as not to exceed 0.25 AI/hour sprayed. With this in mind, no more than just over 3.4 hours per day is needed to apply the actual average flow rate. This is an ideal situation, which we all know does not exist. Therefore, we will operate the spray system more than the 3.4 hours per day at times when operating our facility.



Actual Average Flow

Calculations

for the


Storage Facility

- 4,945,600 Gallons Storage Capacity
- 15,389,426 GPY Average Flow for Previous Five (5) Years
- Current Average Flow Rate = 117.3 Days Storage

If the storage facility were used for the maximum amount of time during inclement weather, then the total gallons (15,389,426) actual average flow for the year would be sprayed during 247.7 (365-117.3) days of the year rather than the full calendar year of 365 days.

- $15,389,624 \div 247.7 \text{ days} = 62,130 \text{ Gallons/Day Sprayed}$
- $62,130 \text{ GPD} \div 27,154 \text{ Gallons/Acre Inch} = 2.29 \text{ AI/Day}$
- $2.29 \text{ AI/Day} \div 13.57 \text{ Spray Acres} = 0.169 \text{ AI/Acre/Day}$
- $0.169 \text{ AI/Acre/Day} \times 7 \text{ Days/Week} = 1.18 \text{ AI/Week for the spray area}$
- $0.169 \text{ AI/Acre} \times 27,154 \text{ Gallons/Acre Inch} = 4,589 \text{ Gallons/Day/Acre}$

Using the pump operating ranges of 308 GPM to 538 GPM, the spray time needed to apply the 4,589 GPA would range from less than 10 minutes to 15 minutes per day. The most restrictive soil zone has a permeability range of 0.6-6.0 inches per hour. The 0.169 AI of spray water is less than 1/3 of the water quantity, which the most restrictive layer of soil can handle. Even when the rainwater is added into the calculations, it will not impact the ability of the soil to handle the total amount on a daily basis. By operating each of the three (3) sections of the spray field on a rotation of once every three (3) days at 0.51 AI/Day of spraying (spray one day and rest two days), we have the capacity to spray the actual average flow using the current storage capacity. We will operate the spray system at a rate so as not to exceed 0.25 AI/hour sprayed. With this in mind, no more than just over 2 hours per day is needed to apply the actual average flow rate. This is an ideal situation, which we all know does not exist. Therefore, we will operate the spray system more than the 2 hours per day at times when operating our facility.



Occoquan Forest STP

Spray Water from Storage Lagoon

Available Nutrients

Design Flow

32,120,000 Gallons per Year Applied

Nitrogen = 7.41 mg/l TKN	$32.12 \text{ MG} \times 8.34 \text{ \#/G H}_2\text{O} \times 7.41 = 1985.0 \text{ lbs.}$
3.14 mg/l NH ₃	$32.12 \text{ MG} \times 8.34 \text{ \#/G H}_2\text{O} \times 3.14 = 841.1 \text{ lbs.}$
4.27 mg/l Org N	$32.12 \text{ MG} \times 8.34 \text{ \#/G H}_2\text{O} \times 4.27 = 1143.6 \text{ lbs.}$
0.61 mg/l NO ₃	$32.12 \text{ MG} \times 8.34 \text{ \#/G H}_2\text{O} \times 0.61 = 163.4 \text{ lbs.}$
Phosphorus = 2.70 mg/l PO ₄	$32.12 \text{ MG} \times 8.34 \text{ \#/G H}_2\text{O} \times 2.70 = 723.3 \text{ lbs.}$
Potassium = 10.89 mg/l K	$32.12 \text{ MG} \times 8.34 \text{ \#/G H}_2\text{O} \times 10.89 = 2917.2 \text{ lbs.}$

Total Available Nitrogen (PA-N)


1143.60 lbs. Organic Nitrogen
<u>0.30 % Mineralization</u>
343.08 lbs. Available Organic Nitrogen
420.55 lbs. Ammonia Nitrogen
<u>163.40 lbs. Nitrate Nitrogen</u>
927.03 lbs. Total Nitrogen
<u>185.41 lbs. Denitrification (20 % loss)</u>

741.62 lbs. Total PA-N

Total Residual Nitrogen from Previous Years Application

2 nd year mineralization @ 0.15 availability	=	120.08 lbs.
3 rd year mineralization @ 0.08	=	54.44 lbs.
4 th year mineralization @ 0.04	=	25.04 lbs.
5 th year mineralization @ 0.04	=	24.04 lbs.
6 th year mineralization @ 0.04	=	23.08 lbs.
7 th year mineralization @ 0.04	=	22.15 lbs.
8 th year mineralization @ 0.04	=	21.27 lbs.
9 th year mineralization @ 0.04	=	20.42 lbs.
10 th year mineralization @ 0.04	=	<u>19.60 lbs.</u>
		330.12 lbs.

$741.62 + 330.12 = 1,071.74 \text{ lbs. Total Nitrogen} \div 13.57 \text{ Acres} = 78.98 \text{ \# N/Acre}$




Occoquan Forest STP

Annual Averages

**Nutrients Applied
(mg/l)**

Year	TKN	NO₃	NH₄	PO₄	K
1995	6.29	1.00	1.68	2.11	8.66
1996	7.48	0.52	2.69	2.12	7.13
1997	5.07	1.60	0.56	2.02	8.72
1998	5.63	0.90	1.81	2.73	10.72
1999	6.89	0.53	1.73	2.37	11.63
2000	6.76	0.65	1.88	3.38	10.95
2001	8.57	0.82	4.25	3.14	11.46
2002	7.50	0.66	3.41	2.46	12.48
2003	7.32	0.36	4.45	2.16	7.92
9 year average (1995-2003)	6.83	0.78	2.50	2.50	9.96
5 year average (1999-2003)	7.41	0.61	3.14	2.70	10.89



Schedule

Effluent Spray Events

Design Flow

North Field
4.99 Acres
x 0.85 AI/Day
4.2415 AI
x 27.154 G/AI
115,174 G/Field

Middle Field
3.37 Acres
x 0.85 AI/Day
2.8645 AI
x 27.154 G/AI
77,783 G/Field

South Field
5.21 acres
x 0.85 AI/Day
4.4285 AI
x 27.154 G/AI
120,251 G/Field

Spraying will occur 44.1 weeks per year when 56.2 days of storage is used. Each weekly spray schedule will occur 14.7 weeks per year.

Weeks Occurring
1, 4, 7, 10, 13, 16,
19, 22, 25, 28, 31,
34, 37, 40, 43

Weeks Occurring
2, 5, 8, 11, 14, 17,
20, 23, 26, 29, 32,
35, 38, 41, 44

Weeks Occurring
3, 6, 9, 12, 15, 18,
21, 24, 27, 30, 33,
36, 39, 42

Day	Gallons
1	115,350
2	77,552
3	116,654
4	115,350
5	77,552
6	116,654
7	115,350

Day	Gallons
1	77,552
2	116,654
3	115,350
4	77,552
5	116,654
6	115,350
7	77,552

Day	Gallons
1	116,654
2	115,350
3	77,552
4	116,654
5	115,350
6	77,552
7	116,654

Total 734,462

Total 696,664

Total 735,766

x 14.7 weeks

x 14.7 weeks


x 14.7 weeks

10,796,591

10,240,960

10,815,760

31,853,311
Total Gallons Sprayed



Schedule

Effluent Spray Events

Actual Flow

North Field
4.99 Acres
x 0.51 AI/Day
2.5449 AI
x 27,154 G/AI
69,104 G/Field

Middle Field
3.37 Acres
x 0.51 AI/Day
1.7187 AI
x 27,154 G/AI
46,670 G/Field

South Field
5.21 acres
x 0.51 AI/Day
2.6571 AI
x 27,154 G/AI
72,151 G/Field

Spraying will occur 35.4 weeks per year when 117.3 days of storage is used. Each weekly spray schedule will occur 11.8 weeks per year.

Weeks Occurring
1, 4, 7, 10, 13, 16,
19, 22, 25, 28, 31,
34

Weeks Occurring
2, 5, 8, 11, 14, 17,
20, 23, 26, 29, 32,
35

Weeks Occurring
3, 6, 9, 12, 15, 18,
21, 24, 27, 30, 33,

Day	Gallons
1	69,104
2	46,670
3	72,151
4	69,104
5	46,670
6	72,151
7	69,104

Day	Gallons
1	46,670
2	72,151
3	69,104
4	46,670
5	72,151
6	69,104
7	46,670

Day	Gallons
1	72,151
2	69,104
3	46,670
4	72,151
5	69,104
6	46,670
7	72,151

Total 444,954

Total 422,520

Total 448,001

x 11.8 weeks

x 11.8 weeks

x 11.8 weeks


5,250,457

4,985,736

5,286,412

15,522,605

Total Gallons Sprayed



Occoquan Forest STP

Water Balance

Month (1)	ET (2)	Precip (3)	Net ET (4) (2-3)	Perc (5)	Hyd Load (6) (4+5)
January	1.2	2.30	-1.10	17.28	16.18
February	1.6	2.35	-0.75	17.28	16.53
March	2.1	2.99	-0.89	17.28	16.39
April	3.3	2.88	0.42	17.28	17.70
May	3.8	3.57	0.33	17.28	17.61
June	4.7	3.43	1.27	17.28	18.55
July	5.3	3.42	1.88	17.28	19.16
August	4.6	3.64	0.96	17.28	18.24
September	3.8	3.27	0.53	17.28	17.81
October	3.0	2.83	0.17	17.28	17.45
November	2.2	2.56	-0.36	17.28	16.92
December	1.4	3.01	-1.61	17.28	15.67
Totals	37.0	36.25	0.85	207.36	208.21

Weather Data The precipitation data is as provided in the Price William County Soil Survey on page 156 as well as from the Virginia Nutrient Management Standards and Criteria on page 61. The evaporation data is from the Water Atlas of the United States which the USDA Soil Conservation Service uses.

Percolation Soil permeability per the Prince William County Soil Survey is 0.6-6.0 inches/hour. Based on field evaluations, the conservative value of 0.6 inches per hour is used. EPA guidelines indicate the use of 4%-10% of allowable infiltration rate for use in design of a system. Therefore:

$$0.6 \text{ inches/hour} \times 24 \text{ hours/day} \times 30 \text{ days/month} \times 0.04 = 17.28 \text{ inches/month}$$

Based on the above information, hydraulic loading is not restrictive.

Prince William County Service Authority
Occoquan Forest STP

Summary
Trace Element Addition

2003

Parameter	Maximum Trace Element #/A	Recoverable Trace Element mg/l	South SF 3 #/A	Site-Life Years	Middle SF 2 #/A	Site-Life Years	North SF 1 #/A	Site-Life Years
Cadmium (Cd)	35	< 0.0005	0.003	11,677	0.003	11,667	0.003	11,667
Copper (Cu)	1,340	0.012	0.077	17,403	0.063	21,270	0.071	18,873
Lead (Pb)	270	<0.004	<0.026	10,385	<0.021	12,857	<0.024	11,250
Nickel (Ni)	375	<0.004	<0.026	14,423	<0.021	17,857	<0.024	15,625
Zinc (Zn)	2,500	0.012	0.077	32,468	0.063	39,683	0.071	35,211

Lifetime (site-life) limits are calculated by dividing the trace element applied (**bold number**) into the maximum allowable pounds per acre of the trace element.

The total recoverable trace element numbers used are found in the attached **Report Form #2** from this 2003 Annual Report.


The lifetime (site-life) will be restricted by Lead. At these levels of trace element addition, it will take **10,385** years to reach the maximum allowable pounds per acre of lead.

Pounds per acre applied of the trace element is calculated by multiplying the wastewater applied (in million gallons [MG]) times the weight of water (8.34 pounds per gallon) times the mg/l of the recoverable trace element.

ATTACHMENT 6


PART D-1, ITEMS 12, 13, AND 14
SITE CHARACTERIZATION






LOCATION MAP

Prince William County Service Authority
Occoquan Forest STP
Land Treatment System






- SW Surface Water Monitoring Site
- MW Existing Monitoring Wells
- NMW New Monitoring Wells
- NEMW New Monitoring Well (existing potable)

ATTACHMENT 7

PART D-1, ITEMS 15 AND 16, SOIL SURVEY
MAP AND SOIL BORINGS




Scale 1:15 840



SOIL MAP

Prince William County Service Authority
Occoquan Forest STP
Land Treatment System



SOIL LEGEND

Publication symbols consist of numbers or a combination of numbers and letters (e.g., 1A, 24C, or 55E). The initial numbers represent the kinds of soil. A capital letter of A, B, C, D, or E, following the first number indicates the class of slope. A final number 3, indicates the unit is severely eroded.

SYMBOL	NAME	SYMBOL	NAME
1A	Aden silt loam, 0 to 2 percent slopes	30B	Jackland silt loam, 2 to 7 percent slopes
2B	Airmont-Weverton complex, 2 to 7 percent slopes	31B	Jackland-Haymarket complex, 2 to 7 percent slopes
2C	Airmont-Weverton complex, 7 to 15 percent slopes	31C	Jackland-Haymarket complex, 7 to 15 percent slopes
2D	Airmont-Weverton complex, 15 to 25 percent slopes		
2E	Airmont-Weverton complex, 25 to 50 percent slopes	32A	Kelly silt loam, 0 to 2 percent slopes
3A	Albano silt loam, 0 to 4 percent slopes		
4B	Arcole silt loam, 2 to 7 percent slopes	33B	Lagone-Oakhill complex, 2 to 7 percent slopes
5C	Arcole-Nestoria complex, 7 to 15 percent slopes	33C	Lagone-Oakhill complex, 7 to 15 percent slopes
5D	Arcole-Nestoria complex, 15 to 25 percent slopes	33D	Lagone-Oakhill complex, 15 to 25 percent slopes
		34B	Lunt loam, 2 to 7 percent slopes
6A	Baile loam, 0 to 4 percent slopes	34C	Lunt loam, 7 to 15 percent slopes
7A	Bermudian silt loam, 0 to 2 percent slopes	34D	Lunt loam, 15 to 25 percent slopes
8C	Braddock loam, 7 to 15 percent slopes		
9B	Brentsville sandy loam, 2 to 7 percent slopes	35B	Manassas silt loam, 2 to 7 percent slopes
9C	Brentsville sandy loam, 7 to 15 percent slopes	36D	Marr very fine sandy loam, 7 to 25 percent slopes
10B	Buckhall loam, 2 to 7 percent slopes	36E	Marr very fine sandy loam, 25 to 50 percent slopes
10C	Buckhall loam, 7 to 15 percent slopes	37A	Marumaco loam, 0 to 4 percent slopes
		38B	Meadowville loam, 0 to 5 percent slopes
11B	Calverton silt loam, 0 to 7 percent slopes	39B3	Minnerville clay loam, 2 to 7 percent slopes, severely eroded
12D	Cattlett gravelly silt loam, 15 to 25 percent slopes	39C3	Minnerville clay loam, 7 to 15 percent slopes, severely eroded
13B	Cattlett-Sycoline complex, 2 to 7 percent slopes	40B	Montalto silty clay loam, 2 to 7 percent slopes
13C	Cattlett-Sycoline complex, 7 to 15 percent slopes	40C	Montalto silty clay loam, 7 to 15 percent slopes
14A	Codorus loam, 0 to 2 percent slopes		
15A	Comus loam, 0 to 2 percent slopes	41B	Neesbaco loam, 0 to 7 percent slopes
		41C	Neesbaco loam, 7 to 15 percent slopes
16A	Delanco fine sandy loam, 0 to 4 percent slopes	42B	Neesbaco-Quantico complex, 2 to 7 percent slopes
17A	Dulles silt loam, 0 to 4 percent slopes	43D	Nestoria gravelly silt loam, 7 to 25 percent slopes
18C	Dumfries sandy loam, 7 to 15 percent slopes	43E	Nestoria gravelly silt loam, 25 to 50 percent slopes
18D	Dumfries sandy loam, 15 to 25 percent slopes		
18E	Dumfries sandy loam, 25 to 50 percent slopes	44D	Ocoquan sandy loam, 7 to 25 percent slopes
		44E	Ocoquan sandy loam, 25 to 50 percent slopes
19B	Eliask loam, 2 to 7 percent slopes	45C	Oranda loam, 7 to 15 percent slopes
19C	Eliask loam, 7 to 15 percent slopes		
20B	Elsinboro sandy loam, 2 to 7 percent slopes	46B	Panorama silt loam, 2 to 7 percent slopes
		46C	Panorama silt loam, 7 to 15 percent slopes
21B	Fairfax loam, 2 to 7 percent slopes		
21C	Fairfax loam, 7 to 15 percent slopes	47B	Quantico sandy loam, 2 to 7 percent slopes
22A	Featherstone silt loam, 0 to 1 percent slopes	47C	Quantico sandy loam, 7 to 15 percent slopes
		47D	Quantico sandy loam, 15 to 25 percent slopes
23C	Gaile sandy loam, 7 to 15 percent slopes		
23D	Gaile sandy loam, 15 to 25 percent slopes	48A	Reaville silt loam, 0 to 4 percent slopes
23E	Gaile sandy loam, 25 to 50 percent slopes	49A	Rowland silt loam, 0 to 2 percent slopes
24B	Glennig-Buckhall complex, 2 to 7 percent slopes		
24C	Glennig-Buckhall complex, 7 to 15 percent slopes	50D	Spriggs silt loam, 15 to 25 percent slopes
24D	Glennig-Buckhall complex, 15 to 25 percent slopes	50E	Spriggs silt loam, 25 to 50 percent slopes
25A	Glenville loam, 0 to 4 percent slopes	51D	Stumptown very flaggy loam, 7 to 25 percent slopes
		51E	Stumptown very flaggy loam, 25 to 50 percent slopes
26A	Hatboro silt loam, 0 to 2 percent slopes	52B	Sudley-Oatlands complex, 2 to 7 percent slopes
27A	Hatboro-Codorus complex, 0 to 2 percent slopes	52C	Sudley-Oatlands complex, 7 to 15 percent slopes
28B	Haymarket silt loam, 2 to 7 percent slopes	53B	Sycoline-Kelly complex, 2 to 7 percent slopes
28C	Haymarket silt loam, 7 to 15 percent slopes	53C	Sycoline-Kelly complex, 7 to 15 percent slopes
29B	Hoadly loam, 2 to 7 percent slopes		
		54B	Urban land-Udorthents complex, 0 to 7 percent slopes
		55D	Watt channery silt loam, 15 to 25 percent slopes
		55E	Watt channery silt loam, 25 to 50 percent slopes
		56A	Waxpool silt loam, 0 to 2 percent slopes

SOIL BORING INFORMATION SHEET


SITE: Occoquan Forest STP

Boring	Soil Type	Depth to		Permeability			Texture		
		Bedrock (inches)	High H ₂ O Table (inches)	Depth (inches)	Surface (inches/hr)	Sub-Surface (inches/hr)	Depth (inches)	Surface	Sub-Surface
1, 2, 4, 5, 7, 8, 9, 12, 14, 15	Elioak	>60	>72	0 - 5 5 - 41 41 - 72	0.6 - 2.0	0.6 - 2.0 0.6 - 2.0	0 - 5	loam	silty clay loam, clay loam, silty clay silt loam, loam, gravelly fine sandy loam
3, 11	Gaila	>60	>72	0 - 7 7 - 15 15 - 43 43 - 72	2.0 - 6.0	0.6 - 2.0 2.0 - 6.0 2.0 - 6.0	0 - 7 7 - 15 15 - 43 43 - 72	sandy loam	sandy clay loam, loam, sandy loam sandy loam, loam loamy sand, sandy loam, loam
6, 10, 13	Glenelg	>60	>72	0 - 5 5 - 20 20 - 65	0.6 - 2.0	0.6 2.0 0.6 - 2.0	0 - 5 5 - 20 20 - 65	loam	channery silt loam, silty clay loam, loam loam, sandy loam, channery loam

On site borings verified all three soil types in the spray fields. The predominant soil was Elioak with some Galia and Glenelg occurring on an infrequent basis along the border areas of the spray fields.

DRAINAGE DITCH DETAIL

10 SCALE



REGRADE AS NECESSARY TO ASSURE THAT IRRIGATION WATER DOES NOT CROSS THE DRAINAGE LINE

RESERVE SPRAY AREA-TYPICAL
LOCATION OF WARNING SIGNS (C APPROX. 300 FT INTERVALS SEE SHEET 2 OF 3 FOR DETAIL)
EXISTING DRAINAGE DITCH RESTORE AS REQUIRED SEE DETAIL

NORTH

BRANCH

EXISTING DRAINAGE DITCH
NEW DITCH LEFT STATION

PERFORMANCE DATA BASED ON FIELD MEASUREMENTS

C-2000	
TOTAL	1.07
North Branch	0.57
Middle Branch	0.30
South Branch	0.20
TOTAL IRRIGATION AREA	
Total Irrigation Area	11.25 acres
Effective Spray Area	13.57 acres
MIDDLE BRANCH IRRIGATION AREA	
Total Irrigation Area	5.31 acres
Effective Spray Area	6.39 acres
SOUTH BRANCH IRRIGATION AREA	
Total Irrigation Area	3.57 acres
Effective Spray Area	3.37 acres
NORTH BRANCH IRRIGATION AREA	
Total Irrigation Area	5.37 acres
Effective Spray Area	5.51 acres
LEAKAGE DATA	
Total	105,374 gal/day
North Branch	58,732 gal/day
Middle Branch	28,510 gal/day
South Branch	18,132 gal/day
LEAKAGE PERCENTAGE	
North Branch	53% @ 7.60 psi
Middle Branch	50% @ 7.75 psi
South Branch	52% @ 8.00 psi
PIPING CAPACITY	
Total Capacity	85,000 gal/day
Storage	15.2 days

IRRIGATION AREA - PLAN

SCALE: 1" = 80'-0"

BRANCH PIPE CONNECTION DETAIL


10 SCALE

NOZZLE INSTALLATION DETAIL

10 SCALE

Continuation of Project
Site Plan
Sheet 2 of 3
CH2M HILL

10 SCALE



AREA TO BE CLEARED OF UNDERBRUSH FOR A RADIUS OF 10' FROM CENTER OF SPRAY NOZZLE AND REMOVED FOR SPRAYING SPEED WITH THE RESUME.

10 SCALE

Rezek, Henry, Meisenheimer, and Gende, Inc. — Libertyville, Illinois

Occoquan Forest Water And Sewer Company


AS-BUILT

NOT FOR CONSTRUCTION - ALL RIGHTS RESERVED

MODIFICATION TO IRRIGATION SYSTEM

JOB NO. 77013
DATE: JUNE 1983

1013



Occoquan Forest STP

Soils

Water Holding Capacity

Soil Type	Horizon Depth	Available Capacity	Average Capacity	Inches Water
Elioak	0 - 5	0.12 - 0.24	0.18	0.90
	5 - 41	0.08 - 0.12	0.10	3.60
	41 - 72	0.08 - 0.10	0.09	<u>2.79</u>
				7.29
Galia	0 - 7	0.10 - 0.12	0.11	0.77
	7 - 15	0.10 - 0.18	0.14	1.22
	15 - 43	0.10 - 0.16	0.13	3.64
	43 - 72	0.08 - 0.14	0.11	<u>3.19</u>
				8.72
Glenelg	0 - 5	0.14 - 0.24	0.19	0.95
	5 - 20	0.10 - 0.20	0.15	2.25
	20 - 65	0.10 - 0.19	0.14	<u>6.30</u>
				9.50

The most restrictive soil zone has the capacity to handle **0.282** Acre Inches (AI) per Day of design/permitted flow capacity.

ATTACHMENT 8

PART D-1, ITEM 17, SOIL ANALYSIS

VPA MONITORING REPORT - Occoquan Forest WWTP
VPA Permit No. VPA0007

FORM 3 - Page 1 of 2

Soil Monitoring

LOCATION; South_SF - 1 Application Sites

Parameter (1)	Available Phosphorus	Cation Exchange Capacity (CEC)	Exchangeable Calcium	Exchangeable Magnesium	Exchangeable Potassium	Exchangeable Sodium	Exchangeable Sulfur	NH ₃ -N	Organic Nitrogen
Limit	NL	NL	NL	NL	NL	NL	NL	NL	NL
Unit	ppm	meq/100 g	ppm	ppm	ppm	ppm	ppm	ppm	ppm
Frequency	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year
Sample Type	Composite	Composite	Composite	Composite	Composite	Composite	Composite	Composite	Composite
Required Reporting	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year
October, 2010	33	7.1	1,015	114	114	75	5	3.8	1,130
October, 2011	38	9.7	1,608	129	129	63	8	3.5	1,200
October, 2012	26	7.4	1,118	124	140	74	10	6.5	1,270
October, 2013	31	7.0	996	112	149	56	8	2.6	1,209
October, 2014	25	7.0	997	115	139	82	10	1.2	1,209

Parameter (1)	Total Nitrogen	Soil Organic Matter	Base Saturation	Exchangeable Sodium Percentage	Acidity	pH	Hydraulic Conductivity	Boron (3)	Chloride (3)
Limit	NL	NL	NL	NL	NL	NL	NL	NL	NL
Unit	ppm	meq/100 g	ppm	ppm	ppm	ppm	ppm	ppm	ppm
Frequency	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/5 Years	1/3 Years	1/3 Years
Sample Type	Composite	Composite	Composite	Composite	Composite	Composite	Composite	Composite	Composite
Required Reporting	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/5 Years	1/3 Years	1/3 Years
October, 2010	1,130	2.5	5.9	4.6	0.4	6.6	See Report	0.9	51
October, 2011	1,200	2.9	0.0	2.8	0.0	7.1	N/A	1.0	27
October, 2012	1,280	3.8	1.4	4.3	0.1	6.9	N/A	0.8	24
October, 2013	1,210	4.2	5.9	3.5	0.4	6.6	N/A	0.7	18
October, 2014	1,210	4.1	4.5	5.1	0.3	6.7	N/A	0.8	36

VPA MONITORING REPORT - Occoquan Forest WWTP
VPA Permit No. VPA0007

FORM 3 - Page 2 of 2

Soil Monitoring

LOCATION; South SF - 1 Application Sites

Parameter (1)	Molybdenum (3)	Copper (3)	Cobalt (3)	Iron (3)	Manganese (3)	Nickel (3)	Zinc (3)	Particle Size Analysis or USDA Textural Estimate (2)
Limit	NL	NL	NL	NL	NL	NL	NL	NL
Unit	ppm	ppm	ppm	ppm	ppm	ppm	ppm	Percent
Frequency	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/5 Years
Sample Type	Composite	Composite	Composite	Composite	Composite	Composite	Composite	Composite
Required Reporting	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/5 Years
October, 2010	<5	7	10	9,030	351	<5	18	36:44:20 Loam
October, 2011	<5	10	9	10,700	440	5	22	47:34:20 Loam
October, 2012	<5	8	12	9,930	484	5	26	40:44:19 Loam
October, 2013	<5	5	7	8,050	368	<5	13	42:38:20 Loam
October, 2014	<5	10	9	12,100	349	7	29	46:38:16 Loam

(1) Soil samples shall be collected in October and results submitted by January 10th of the following year as outlined in the O & M Manual.

(2) Hydraulic conductivity testing and particle size analysis are to be conducted every five years.

(3) Sampling for micronutrients shall be conducted triennially. All metals are to be reported as total metals.

Legend: NL = No Limit (monitoring requirement only)

VPA MONITORING REPORT - Occoquan Forest WWTP
VPA Permit No. VPA0007

FORM 3 - Page 1 of 2

Soil Monitoring

LOCATION; South_SF - 2 Application Sites

Parameter (1)	Available Phosphorus	Cation Exchange Capacity (CEC)	Exchangeable Calcium	Exchangeable Magnesium	Exchangeable Potassium	Exchangeable Sodium	Exchangeable Sulfur	NH ₃ -N	Organic Nitrogen
Limit	NL	NL	NL	NL	NL	NL	NL	NL	NL
Unit	ppm	meq/100 g	ppm	ppm	ppm	ppm	ppm	ppm	ppm
Frequency	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year
Sample Type	Composite	Composite	Composite	Composite	Composite	Composite	Composite	Composite	Composite
Required Reporting	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year
October, 2010	39	8.4	1,258	124	100	72	6	4.0	1,450
October, 2011	22	8.2	1,181	135	114	60	7	5.5	1,310
October, 2012	17	6.7	953	111	128	69	12	4.3	1,120
October, 2013	21	6.8	972	113	122	56	6	1.7	1,020
October, 2014	16	6.8	946	114	128	65	12	2.4	1,178

Parameter (1)	Total Nitrogen	Soil Organic Matter	Base Saturation	Exchangeable Sodium Percentage	Acidity	pH	Hydraulic Conductivity	Boron (3)	Chloride (3)
Limit	NL	NL	NL	NL	NL	NL	NL	NL	NL
Unit	ppm	meq/100 g	ppm	ppm	ppm	ppm	ppm	ppm	ppm
Frequency	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/5 Years	1/3 Years	1/3 Years
Sample Type	Composite	Composite	Composite	Composite	Composite	Composite	Composite	Composite	Composite
Required Reporting	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/5 Years	1/3 Years	1/3 Years
October, 2010	1,450	3.4	5.9	3.7	0.5	6.6	See Report	0.8	50
October, 2011	1,310	3	7.4	3.2	0.6	6.5	N/A	0.6	31
October, 2012	1,120	2.8	5.9	4.5	0.4	6.8	N/A	0.7	25
October, 2013	1,020	3.9	5.9	3.6	0.4	6.8	N/A	0.7	18
October, 2014	1,180	4.4	7.4	4.2	0.5	6.5	N/A	0.6	2.1

VPA MONITORING REPORT - Occoquan Forest WWTP
VPA Permit No. VPA0007

FORM 3 - Page 2 of 2

Soil Monitoring

LOCATION; South_SF - 2 Application Sites

Parameter (1)	Molybdenum (3)	Copper (3)	Cobalt (3)	Iron (3)	Manganese (3)	Nickel (3)	Zinc (3)	Particle Size Analysis or USDA Textural Estimate (2)
Limit	NL	NL	NL	NL	NL	NL	NL	NL
Unit	ppm	ppm	ppm	ppm	ppm	ppm	ppm	Percent
Frequency	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/5 Years
Sample Type	Composite	Composite	Composite	Composite	Composite	Composite	Composite	Composite
Required Reporting	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/5 Years
October, 2010	<5	6	6	9,770	196	<5	11	34:46:20 Loam
October, 2011	<5	11	7	10,400	191	<5	18	43:34:24 Loam
October, 2012	<5	10	7	11,100	199	<5	19	40:39:21 Loam
October, 2013	<5	7	6	7,080	200	<5	13	40:43:17 Loam
October, 2014	<5	13	7	13,600	201	5	26	44:38:18 Loam

(1) Soil samples shall be collected in October and results submitted by January 10th of the following year as outlined in the O & M Manual.

(2) Hydraulic conductivity testing and particle size analysis are to be conducted every five years.

(3) Sampling for micronutrients shall be conducted triennially. All metals are to be reported as total metals.

Legend: NL = No Limit (monitoring requirement only)

VPA MONITORING REPORT - Occoquan Forest WWTP
VPA Permit No. VPA0007

FORM 3 - Page 1 of 2

Soil Monitoring

LOCATION; South_SF - 3 Application Sites

Parameter (1)	Available Phosphorus	Cation Exchange Capacity (CEC)	Exchangeable Calcium	Exchangeable Magnesium	Exchangeable Potassium	Exchangeable Sodium	Exchangeable Sulfur	NH ₃ -N	Organic Nitrogen
Limit	NL	NL	NL	NL	NL	NL	NL	NL	NL
Unit	ppm	meq/100 g	ppm	ppm	ppm	ppm	ppm	ppm	ppm
Frequency	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year
Sample Type	Composite	Composite	Composite	Composite	Composite	Composite	Composite	Composite	Composite
Required Reporting	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year
October, 2010	64	9.5	1,495	121	112	72	5	4.0	1,390
October, 2011	35	7.3	1,071	109	112	67	9	2.1	1,150
October, 2012	34	6	864	96	138	88	13	4.7	855
October, 2013	40	6.4	883	100	144	77	13	1.4	839
October, 2014	39	6.6	984	101	130	71	9	2.3	1,088

Parameter (1)	Total Nitrogen	Soil Organic Matter	Base Saturation	Exchangeable Sodium Percentage	Acidity	pH	Hydraulic Conductivity	Boron (3)	Chloride (3)
Limit	NL	NL	NL	NL	NL	NL	NL	NL	NL
Unit	ppm	meq/100 g	ppm	ppm	ppm	ppm	ppm	ppm	ppm
Frequency	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/5 Years	1/3 Years	1/3 Years
Sample Type	Composite	Composite	Composite	Composite	Composite	Composite	Composite	Composite	Composite
Required Reporting	1/Year	1/Year	1/Year	1/Year	1/Year	1/Year	1/5 Years	1/3 Years	1/3 Years
October, 2010	1,390	3.7	4.5	3.3	0.4	6.7	See Report	0.9	51
October, 2011	1,150	2.9	5.9	4.0	0.4	6.6	N/A	0.7	41
October, 2012	860	2.2	2.9	6.4	0.2	6.8	N/A	1.0	28
October, 2013	840	3.8	7.4	5.2	0.5	6.5	N/A	0.2	22
October, 2014	1,090	4.0	2.9	4.7	0.2	6.8	N/A	0.7	25

VPA MONITORING REPORT - Occoquan Forest WWTP
VPA Permit No. VPA0007

FORM 3 - Page 2 of 2

Soil Monitoring

LOCATION; South_SF - 3 Application Sites

Parameter (1)	Molybdenum (3)	Copper (3)	Cobalt (3)	Iron (3)	Manganese (3)	Nickel (3)	Zinc (3)	Particle Size Analysis or USDA Textural Estimate (2)
Limit	NL	NL	NL	NL	NL	NL	NL	NL
Unit	ppm	ppm	ppm	ppm	ppm	ppm	ppm	Percent
Frequency	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/5 Years
Sample Type	Composite	Composite	Composite	Composite	Composite	Composite	Composite	Composite
Required Reporting	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/3 Years	1/5 Years
October, 2010	<5	4		7,210	50	<5	16	52:36:12 Sandy Loam
October, 2011	<5	11	8	8,970	307	5	23	38:44:18 Loam
October, 2012	<5	12	8	12,300	281	5	26	41:40:19 Loam
October, 2013	<5	7	7	8,650	209	5	13	42:39:19 Loam
October, 2014	<5	15	10	12,500	289	8	31	44:42:14 Loam

(1) Soil samples shall be collected in October and results submitted by January 10th of the following year as outlined in the O & M Manual.

(2) Hydraulic conductivity testing and particle size analysis are to be conducted every five years.

(3) Sampling for micronutrients shall be conducted triennially. All metals are to be reported as total metals.

Legend: NL = No Limit (monitoring requirement only)

Report Number: 14-287-0655

Account Number: 25273



www.aleastern.com

A&L Eastern Laboratories

7621 Whitepine Road Richmond, Virginia 23237 (804) 743-9401 Fax (804) 271-6446

Send To: ENVIRONMENTAL AGRONOMICS
POB 120
QUANTICO MD 21856

Grower:
PRINCE WILLIAM COUNTY SERV
OCCOQUAN FOREST STP

Submitted By: D L JARRETT
Farm ID:

SOIL ANALYSIS REPORT

Analytical Method(s):
Mehlich 3

Date Received: 10/14/2014

Date Of Analysis: 10/15/2014

Date Of Report: 10/20/2014

Sample ID Field ID	Lab Number	Organic Matter			Phosphorus				Potassium		Magnesium		Calcium		Sodium		pH		Acidity		C.E.C	
		%	Rate	ENR lbs/A	Mehlich 3 ppm	Rate	Reserve ppm	Rate	K ppm	Rate	Mg ppm	Rate	Ca ppm	Rate	Na ppm	Rate	Soil pH	Buffer Index	H meq/100g		meq/100g	
SF-1 N SURFACE	24494	4.1	M	122	25	L			139	H	115	M	997	H	82	M	6.7		0.3		7.0	
					MD = 30				MD = 88		MD = 90		MD = 99									
SF-1 N SUBSURF	24495	2.5	L	92	10	VL			121	M	107	H	687	M	92	M	6.2		0.7		5.7	
					MD = 13				MD = 77		MD = 84		MD = 60									
SF-2 MID SURFAC	24496	4.4	M	128	16	L			128	H	114	M	946	M	65	M	6.5		0.5		6.8	
					MD = 20				MD = 81		MD = 89		MD = 93									
SF-2 MID SUBSUF	24497	2.5	L	93	14	L			124	M	97	H	534	M	62	M	5.7	6.82	1.1		5.2	
					MD = 18				MD = 79		MD = 77		MD = 41									
SF-3 S SURFACE	24498	4.0	M	121	39	M			130	H	101	M	984	H	71	M	6.8		0.2		6.6	
					MD = 45				MD = 82		MD = 80		MD = 97									

Sample ID Field ID	Percent Base Saturation					Nitrate		Sulfur		Zinc		Manganese		Iron		Copper		Boron		Soluble Salts		Chloride		Aluminum	
	K %	Mg %	Ca %	Na %	H %	NO ₃ N ppm	Rate	S ppm	Rate	Zn ppm	Rate	Mn ppm	Rate	Fe ppm	Rate	Cu ppm	Rate	B ppm	Rate	SS ms/cm	Rate	Cl ppm	Rate	Al ppm	
SF-1 N SURFACE	5.1	13.7	71.2	5.1	4.5			10	L	2.2	L	85	VH	169	VH	2.1	H	0.8	M	0.11	VL	36			
SF-1 N SUBSURF	5.4	15.6	60.3	7.0	12.2			22	M	1.6	L	67	VH	81	VH	1.8	H	0.6	M	0.12	VL	35			
SF-2 MID SURFAC	4.8	14.0	69.6	4.2	7.4			12	L	1.7	L	40	H	162	VH	1.7	H	0.6	M	0.1	VL	21			
SF-2 MID SUBSUF	6.1	15.5	51.3	5.2	20.9			29	H	1.1	L	35	H	95	VH	1.4	M	0.4	L	0.1	VL	34			
SF-3 S SURFACE	5.1	12.8	74.5	4.7	2.9			9	VL	1.6	L	72	VH	209	VH	2.1	H	0.7	M	0.09	VL	25			

Values on this report represent the plant available nutrients in the soil. Rating after each value: VL (Very Low), L (Low), M (Medium), H (High), VH (Very High). ENR - Estimated Nitrogen Release. C.E.C. - Cation Exchange Capacity.

Explanation of symbols: % (percent), ppm (parts per million), lbs/A (pounds per acre), ms/cm (milli-mhos per centimeter), meq/100g (milli-equivalent per 100 grams). Conversions: ppm x 2 = lbs/A, Soluble Salts ms/cm x 640 = ppm.

This report applies to sample(s) tested. Samples are retained a maximum of thirty days after testing.

Analysis prepared by: A&L Eastern Laboratories, Inc.

by: *Paucie McGeary*

Paucie McGeary

Report Number: 14-287-0655

Account Number: 25273



www.aleastern.com

A&L Eastern Laboratories

7621 Whitepine Road Richmond, Virginia 23237 (804) 743-9401 Fax (804) 271-6446

Send To: ENVIRONMENTAL AGRONOMICS
POB 120
QUANTICO MD 21856

Grower:
PRINCE WILLIAM COUNTY SERV
OCCOQUAN FOREST STP

Submitted By: D L JARRETT
Farm ID:

SOIL ANALYSIS REPORT

Analytical Method(s):
Mehlich 3

Date Received: 10/14/2014

Date Of Analysis: 10/15/2014

Date Of Report: 10/20/2014

Sample ID Field ID	Lab Number	Organic Matter			Phosphorus				Potassium		Magnesium		Calcium		Sodium		pH		Acidity	C.E.C
		%	Rate	ENR lbs/A	Mehlich 3 ppm	Rate	Reserve ppm	Rate	K ppm	Rate	Mg ppm	Rate	Ca ppm	Rate	Na ppm	Rate	Soil pH	Buffer Index	H meq/100g	meq/100g
SF-3 S SUBSURF/	24499	2.3	L	90	14	L			140	VH	84	H	506	M	83	H	6.2		0.5	4.5
					MD = 18				MD = 89		MD = 67		MD = 37							

Sample ID Field ID	Percent Base Saturation					Nitrate	Sulfur	Zinc	Manganese	Iron	Copper	Boron	Soluble Salts	Chloride	Aluminum									
	K %	Mg %	Ca %	Na %	H %	NO ₃ N ppm	Rate	S ppm	Rate	Zn ppm	Rate	Mn ppm	Rate	Fe ppm	Rate	Cu ppm	Rate	B ppm	Rate	SS ms/cm	Rate	Cl ppm	Rate	Al ppm
SF-3 S SUBSURF/	8.0	15.6	56.2	8.0	12.1			12	L	1.1	L	27	H	111	VH	1.5	M	0.5	L	0.08	VL	38		

Values on this report represent the plant available nutrients in the soil. Rating after each value: VL (Very Low), L (Low), M (Medium), H (High), VH (Very High). ENR - Estimated Nitrogen Release. C.E.C. - Cation Exchange Capacity.

Explanation of symbols: % (percent), ppm (parts per million), lbs/A (pounds per acre), ms/cm (milli-mhos per centimeter), meq/100g (milli-equivalent per 100 grams). Conversions: ppm x 2 = lbs/A, Soluble Salts ms/cm x 640 = ppm.

This report applies to sample(s) tested. Samples are retained a maximum of thirty days after testing.

Analysis prepared by: A&L Eastern Laboratories, Inc.

by: *Paucic McGeary*

Paucic McGroary

Report Number

14-287-0655

Page: 1 of 12

Account Number

25273

Send To: ENVIRONMENTAL AGRONOMICS

POB 120

QUANTICO, MD 21856

Project : PRINCE WILLIAM COUNTY SERVICE AUTHORITY

OCCOQUAN FOREST STP



www.aleastern.com

A&L Eastern Laboratories, Inc.

7621 Whitepine Road Richmond, Virginia 23237 (804) 743-9401 Fax (804) 271-6446

Submitted By : D L JARRETT

Purchase Order :

Report Date : 10/20/2014

Date Received : 10/14/2014

REPORT OF ANALYSIS

Date Sampled :

Lab Number: 24494

Sample Id : SF-1 N SURFACE

Analysis	Result	Quantitation Limit	Method	Date and Time Test Started	Analyst
Total Kjeldahl Nitrogen , ppm	1210	10.0	SM-4500-NH3C-TKN	10/15/2014 08:39	JM
Total Iron , ppm	12100	100	SW 6010C	10/17/2014 14:44	KM
Total Manganese , ppm	349	5	SW 6010C	10/17/2014 14:44	KM
Total Copper , ppm	10	5	SW 6010C	10/17/2014 14:44	KM
Total Zinc , ppm	29	5	SW 6010C	10/17/2014 14:44	KM
Total Nickel , ppm	7	5	SW 6010C	10/17/2014 14:44	KM
Total Molybdenum , ppm	<5	5	SW 6010C	10/17/2014 14:44	KM
Total Cobalt , ppm	9	5	SW 6010C	10/17/2014 14:44	KM
Nitrogen, Ammoniacal , ppm	1.2	0.1	SOIL AMMONIA-N	10/15/2014 09:00	RD

Paulie McGroary

Paulie McGroary

Report Number

14-287-0655

Page: 2 of 12

Account Number

25273

Send To: ENVIRONMENTAL AGRONOMICS

POB 120

QUANTICO, MD 21856

Project : PRINCE WILLIAM COUNTY SERVICE AUTHORITY

OCCOQUAN FOREST STP



www.aleastern.com

A&L Eastern Laboratories, Inc.

7621 Whitepine Road Richmond, Virginia 23237 (804) 743-9401 Fax (804) 271-6446

Submitted By : D L JARRETT

Purchase Order :

Report Date : 10/20/2014

Date Received : 10/14/2014

REPORT OF ANALYSIS

Date Sampled :

Lab Number: 24494

Sample Id : SF-1 N SURFACE

Analysis	Result	Quantitation Limit	Method	Date and Time Test Started	Analyst
----------	--------	-----------------------	--------	-------------------------------	---------

Method Reference:

Methods for Chemical Analysis of Water and Wastes, EPA-600/4-79-020, March 1983

Methods of Soil Analysis, Part 1 - Physical and Mineralogical Methods, 2nd Ed. Rev. Soil Science Society of America, Black, C.A et al. 1982, page 40.

Methods of Soil Analysis, Part 3 - Chemical Methods, 2nd Ed. Rev. Soil Science Society of America, Black, C.A et al. 1982, pages 1185-1186.

Recommended Chemical Soil Test Procedures for the North Central Region. NCR Research Pub. No. 221 Revised.

Standard Methods for the Analysis of Water and Wastewater, 1997

USEPA, SW-846, Test Methods for Evaluating Solid Wastes, Physical/Chemical Methods, 3rd Ed. Current Revision

Comments:

Paucic McGeary

Paucic McGroary

Report Number

14-287-0655

Page: 3 of 12

Account Number

25273

Send To: ENVIRONMENTAL AGRONOMICS

POB 120

QUANTICO, MD 21856

Project : PRINCE WILLIAM COUNTY SERVICE AUTHORITY

OCCOQUAN FOREST STP



www.aleastern.com

A&L Eastern Laboratories, Inc.

7621 Whitepine Road Richmond, Virginia 23237 (804) 743-9401 Fax (804) 271-6446

Submitted By : D L JARRETT

Purchase Order :

Report Date : 10/20/2014

Date Received : 10/14/2014

REPORT OF ANALYSIS

Date Sampled :

Lab Number: 24495

Sample Id : SF-1 N SUBSURFACE

Analysis	Result	Quantitation Limit	Method	Date and Time Test Started	Analyst
Total Kjeldahl Nitrogen , ppm	530	10.0	SM-4500-NH3C-TKN	10/15/2014 08:39	JM
Total Iron , ppm	17200	100	SW 6010C	10/17/2014 14:44	KM
Total Manganese , ppm	231	5	SW 6010C	10/17/2014 14:44	KM
Total Copper , ppm	11	5	SW 6010C	10/17/2014 14:44	KM
Total Zinc , ppm	30	5	SW 6010C	10/17/2014 14:44	KM
Total Nickel , ppm	6	5	SW 6010C	10/17/2014 14:44	KM
Total Molybdenum , ppm	<5	5	SW 6010C	10/17/2014 14:44	KM
Total Cobalt , ppm	11	5	SW 6010C	10/17/2014 14:44	KM
Nitrogen, Ammoniacal , ppm	1.8	0.1	SOIL AMMONIA-N	10/15/2014 09:00	RD

Paucic McGroary

Paucic McGroary

Report Number

14-287-0655

Page: 4 of 12

Account Number

25273

Send To: ENVIRONMENTAL AGRONOMICS

POB 120

QUANTICO, MD 21856

Project : PRINCE WILLIAM COUNTY SERVICE AUTHORITY

OCCOQUAN FOREST STP



www.aleastern.com

A&L Eastern Laboratories, Inc.

7621 Whitepine Road Richmond, Virginia 23237 (804) 743-9401 Fax (804) 271-6446

Submitted By : D L JARRETT

Purchase Order :

Report Date : 10/20/2014

Date Received : 10/14/2014

Date Sampled :

Lab Number: 24495

Sample Id : SF-1 N SUBSURFACE

REPORT OF ANALYSIS

Analysis	Result	Quantitation Limit	Method	Date and Time Test Started	Analyst
----------	--------	-----------------------	--------	-------------------------------	---------

Method Reference:

Methods for Chemical Analysis of Water and Wastes, EPA-600/4-79-020, March 1983

Methods of Soil Analysis, Part 1 - Physical and Mineralogical Methods, 2nd Ed. Rev. Soil Science Society of America, Black, C.A et al. 1982, page 40.

Methods of Soil Analysis, Part 3 - Chemical Methods, 2nd Ed. Rev. Soil Science Society of America, Black, C.A et al. 1982, pages 1185-1186.

Recommended Chemical Soil Test Procedures for the North Central Region. NCR Research Pub. No. 221 Revised.

Standard Methods for the Analysis of Water and Wastewater, 1997

USEPA, SW-846, Test Methods for Evaluating Solid Wastes, Physical/Chemical Methods, 3rd Ed. Current Revision

Comments:

Paule McGeary

Paule McGeary

Report Number

14-287-0655

Page: 5 of 12

Account Number

25273

Send To: ENVIRONMENTAL AGRONOMICS

POB 120

QUANTICO, MD 21856

Project : PRINCE WILLIAM COUNTY SERVICE AUTHORITY

OCCOQUAN FOREST STP



www.aleastern.com

A&L Eastern Laboratories, Inc.

7621 Whitepine Road Richmond, Virginia 23237 (804) 743-9401 Fax (804) 271-6446

Submitted By : D L JARRETT

Purchase Order :

Report Date : 10/20/2014

Date Received : 10/14/2014

REPORT OF ANALYSIS

Date Sampled :

Lab Number: 24496

Sample Id : SF-2 MID SURFACE

Analysis	Result	Quantitation Limit	Method	Date and Time Test Started	Analyst
Total Kjeldahl Nitrogen , ppm	1180	10.0	SM-4500-NH3C-TKN	10/15/2014 08:39	JM
Total Iron , ppm	13600	100	SW 6010C	10/17/2014 14:44	KM
Total Manganese , ppm	201	5	SW 6010C	10/17/2014 14:44	KM
Total Copper , ppm	13	5	SW 6010C	10/17/2014 14:44	KM
Total Zinc , ppm	26	5	SW 6010C	10/17/2014 14:44	KM
Total Nickel , ppm	5	5	SW 6010C	10/17/2014 14:44	KM
Total Molybdenum , ppm	<5	5	SW 6010C	10/17/2014 14:44	KM
Total Cobalt , ppm	7	5	SW 6010C	10/17/2014 14:44	KM
Nitrogen, Ammoniacal , ppm	2.4	0.1	SOIL AMMONIA-N	10/15/2014 09:00	RD

Paucic McGroary

Paucic McGroary

Report Number

14-287-0655

Page: 6 of 12

Account Number

25273

Send To: ENVIRONMENTAL AGRONOMICS

POB 120

QUANTICO, MD 21856

Project : PRINCE WILLIAM COUNTY SERVICE AUTHORITY

OCCOQUAN FOREST STP



www.aleastern.com

A&L Eastern Laboratories, Inc.

7621 Whitepine Road Richmond, Virginia 23237 (804) 743-9401 Fax (804) 271-6446

Submitted By : D L JARRETT

Purchase Order :

Report Date : 10/20/2014

Date Received : 10/14/2014

REPORT OF ANALYSIS

Date Sampled :

Lab Number: 24496

Sample Id : SF-2 MID SURFACE

Analysis	Result	Quantitation Limit	Method	Date and Time Test Started	Analyst
----------	--------	-----------------------	--------	-------------------------------	---------

Method Reference:

Methods for Chemical Analysis of Water and Wastes, EPA-600/4-79-020, March 1983

Methods of Soil Analysis, Part 1 - Physical and Mineralogical Methods, 2nd Ed. Rev. Soil Science Society of America, Black, C.A et al. 1982, page 40.

Methods of Soil Analysis, Part 3 - Chemical Methods, 2nd Ed. Rev. Soil Science Society of America, Black, C.A et al. 1982, pages 1185-1186.

Recommended Chemical Soil Test Procedures for the North Central Region. NCR Research Pub. No. 221 Revised.

Standard Methods for the Analysis of Water and Wastewater, 1997

USEPA, SW-846, Test Methods for Evaluating Solid Wastes, Physical/Chemical Methods, 3rd Ed. Current Revision

Comments:

Paucic McGroary

Paucic McGroary

Report Number

14-287-0655

Page: 7 of 12

Account Number

25273

Send To: ENVIRONMENTAL AGRONOMICS

POB 120

QUANTICO, MD 21856

Project : PRINCE WILLIAM COUNTY SERVICE AUTHORITY
OCCOQUAN FOREST STP

www.aleastern.com

A&L Eastern Laboratories, Inc.

7621 Whitepine Road Richmond, Virginia 23237 (804) 743-9401 Fax (804) 271-6446

Submitted By : D L JARRETT**Purchase Order :****Report Date :** 10/20/2014**Date Received :** 10/14/2014**REPORT OF ANALYSIS****Date Sampled :**

Lab Number: 24497

Sample Id : SF-2 MID SUBSURFACE

Analysis	Result	Quantitation Limit	Method	Date and Time Test Started	Analyst
Total Kjeldahl Nitrogen , ppm	470	10.0	SM-4500-NH3C-TKN	10/15/2014 08:39	JM
Total Iron , ppm	17500	100	SW 6010C	10/17/2014 14:44	KM
Total Manganese , ppm	171	5	SW 6010C	10/17/2014 14:44	KM
Total Copper , ppm	13	5	SW 6010C	10/17/2014 14:44	KM
Total Zinc , ppm	24	5	SW 6010C	10/17/2014 14:44	KM
Total Nickel , ppm	5	5	SW 6010C	10/17/2014 14:44	KM
Total Molybdenum , ppm	<5	5	SW 6010C	10/17/2014 14:44	KM
Total Cobalt , ppm	12	5	SW 6010C	10/17/2014 14:44	KM
Nitrogen, Ammoniacal , ppm	1.9	0.1	SOIL AMMONIA-N	10/15/2014 09:00	RD

Paulee McGeary

Paulee McGeary

Report Number

14-287-0655

Page: 8 of 12

Account Number

25273

Send To: ENVIRONMENTAL AGRONOMICS

POB 120

QUANTICO, MD 21856

Project : PRINCE WILLIAM COUNTY SERVICE AUTHORITY

OCCOQUAN FOREST STP



www.aleastern.com

A&L Eastern Laboratories, Inc.

7621 Whitepine Road Richmond, Virginia 23237 (804) 743-8401 Fax (804) 271-8446

Submitted By : D L JARRETT

Purchase Order :

Report Date : 10/20/2014

Date Received : 10/14/2014

REPORT OF ANALYSIS

Date Sampled :

Lab Number: 24497

Sample Id : SF-2 MID SUBSURFACE

Analysis	Result	Quantitation Limit	Method	Date and Time Test Started	Analyst
----------	--------	-----------------------	--------	-------------------------------	---------

Method Reference:

Methods for Chemical Analysis of Water and Wastes, EPA-600/4-79-020, March 1983

Methods of Soil Analysis, Part 1 - Physical and Mineralogical Methods, 2nd Ed. Rev. Soil Science Society of America, Black, C.A et al. 1982, page 40

Methods of Soil Analysis, Part 3 - Chemical Methods, 2nd Ed. Rev. Soil Science Society of America, Black, C.A et al. 1982, pages 1185-1186.

Recommended Chemical Soil Test Procedures for the North Central Region. NCR Research Pub. No. 221 Revised.

Standard Methods for the Analysis of Water and Wastewater, 1997

USEPA, SW-846, Test Methods for Evaluating Solid Wastes, Physical/Chemical Methods, 3rd Ed. Current Revision

Comments:

Pauric McGeary

Pauric McGroary

Report Number

14-287-0655

Page: 9 of 12

Account Number

25273

Send To: ENVIRONMENTAL AGRONOMICS
POB 120

QUANTICO, MD 21856

Project : PRINCE WILLIAM COUNTY SERVICE AUTHORITY
OCCOQUAN FOREST STP**A&L Eastern Laboratories, Inc.**

7621 Whitepine Road Richmond, Virginia 23237 (804) 743-9401 Fax (804) 271-6446

Submitted By : D L JARRETT**Purchase Order :****Report Date :** 10/20/2014**Date Received :** 10/14/2014**REPORT OF ANALYSIS****Date Sampled :**

Lab Number: 24498

Sample Id : SF-3 S SURFACE

Analysis	Result	Quantitation Limit	Method	Date and Time Test Started	Analyst
Total Kjeldahl Nitrogen , ppm	1090	10.0	SM-4500-NH3C-TKN	10/15/2014 08:39	JM
Total Iron , ppm	12500	100	SW 6010C	10/17/2014 14:44	KM
Total Manganese , ppm	289	5	SW 6010C	10/17/2014 14:44	KM
Total Copper , ppm	15	5	SW 6010C	10/17/2014 14:44	KM
Total Zinc , ppm	31	5	SW 6010C	10/17/2014 14:44	KM
Total Nickel , ppm	8	5	SW 6010C	10/17/2014 14:44	KM
Total Molybdenum , ppm	<5	5	SW 6010C	10/17/2014 14:44	KM
Total Cobalt , ppm	10	5	SW 6010C	10/17/2014 14:44	KM
Nitrogen, Ammoniacal , ppm	2.3	0.1	SOIL AMMONIA-N	10/15/2014 09:00	RD

Paucic McGroary

Paucic McGroary

Report Number

14-287-0655

Page: 10 of 12

Account Number

25273

Send To: ENVIRONMENTAL AGRONOMICS

POB 120

QUANTICO, MD 21856

Project : PRINCE WILLIAM COUNTY SERVICE AUTHORITY

OCCOQUAN FOREST STP



www.aleastern.com

A&L Eastern Laboratories, Inc.

7621 Whitepine Road Richmond, Virginia 23237 (804) 743-9401 Fax (804) 271-6446

Submitted By : D L JARRETT

Purchase Order :

Report Date : 10/20/2014

Date Received : 10/14/2014

Date Sampled :

Lab Number: 24498

Sample Id : SF-3 S SURFACE

REPORT OF ANALYSIS

Analysis	Result	Quantitation Limit	Method	Date and Time Test Started	Analyst
----------	--------	-----------------------	--------	-------------------------------	---------

Method Reference:

Methods for Chemical Analysis of Water and Wastes, EPA-600/4-79-020, March 1983

Methods of Soil Analysis, Part 1 - Physical and Mineralogical Methods, 2nd Ed. Rev. Soil Science Society of America, Black, C.A et al. 1982, page 40

Methods of Soil Analysis, Part 3 - Chemical Methods, 2nd Ed. Rev. Soil Science Society of America, Black, C.A et al. 1982, pages 1185-1186.

Recommended Chemical Soil Test Procedures for the North Central Region. NCR Research Pub. No. 221 Revised.

Standard Methods for the Analysis of Water and Wastewater, 1997

USEPA, SW-846, Test Methods for Evaluating Solid Wastes, Physical/Chemical Methods, 3rd Ed. Current Revision

Comments:

Paulie McGowan

Paulie McGowan

Report Number

14-287-0655

Page: 11 of 12

Account Number

25273

Send To: ENVIRONMENTAL AGRONOMICS

POB 120

QUANTICO, MD 21856

Project : PRINCE WILLIAM COUNTY SERVICE AUTHORITY

OCCOQUAN FOREST STP



www.aleastern.com

A&L Eastern Laboratories, Inc.

7621 Whitepine Road Richmond, Virginia 23237 (804) 743-9401 Fax (804) 271-6446

Submitted By : D L JARRETT

Purchase Order :

Report Date : 10/20/2014

Date Received : 10/14/2014

REPORT OF ANALYSIS

Date Sampled :

Lab Number: 24499

Sample Id : SF-3 S SUBSURFACE

Analysis	Result	Quantitation Limit	Method	Date and Time Test Started	Analyst
Total Kjeldahl Nitrogen , ppm	410	10.0	SM-4500-NH3C-TKN	10/15/2014 08:39	JM
Total Iron , ppm	15000	100	SW 6010C	10/17/2014 14:44	KM
Total Manganese , ppm	171	5	SW 6010C	10/17/2014 14:44	KM
Total Copper , ppm	15	5	SW 6010C	10/17/2014 14:44	KM
Total Zinc , ppm	30	5	SW 6010C	10/17/2014 14:44	KM
Total Nickel , ppm	6	5	SW 6010C	10/17/2014 14:44	KM
Total Molybdenum , ppm	<5	5	SW 6010C	10/17/2014 14:44	KM
Total Cobalt , ppm	10	5	SW 6010C	10/17/2014 14:44	KM
Nitrogen, Ammoniacal , ppm	2.2	0.1	SOIL AMMONIA-N	10/15/2014 09:00	RD

Pauric McGeary

Pauric McGroary

Report Number

14-287-0655

Page: 12 of 12

Account Number

25273

Send To: ENVIRONMENTAL AGRONOMICS

POB 120

QUANTICO, MD 21856

Project : PRINCE WILLIAM COUNTY SERVICE AUTHORITY

OCCOQUAN FOREST STP



www.aleastern.com

A&L Eastern Laboratories, Inc.

7621 Whitepine Road Richmond, Virginia 23237 (804) 743-9401 Fax (804) 271-6446

Submitted By : D L JARRETT**Purchase Order :****Report Date :** 10/20/2014**Date Received :** 10/14/2014**Date Sampled :****Lab Number:** 24499**Sample Id :** SF-3 S SUBSURFACE**REPORT OF ANALYSIS**

Analysis	Result	Quantitation Limit	Method	Date and Time Test Started	Analyst
-----------------	---------------	-------------------------------	---------------	---------------------------------------	----------------

Method Reference:

Methods for Chemical Analysis of Water and Wastes, EPA-600/4-79-020, March 1983

Methods of Soil Analysis, Part 1 - Physical and Mineralogical Methods, 2nd Ed. Rev. Soil Science Society of America, Black, C.A et al. 1982, page 40.

Methods of Soil Analysis, Part 3 - Chemical Methods, 2nd Ed. Rev. Soil Science Society of America, Black, C.A et al. 1982, pages 1185-1186.

Recommended Chemical Soil Test Procedures for the North Central Region. NCR Research Pub. No. 221 Revised.

Standard Methods for the Analysis of Water and Wastewater, 1997

USEPA, SW-846, Test Methods for Evaluating Solid Wastes, Physical/Chemical Methods, 3rd Ed. Current Revision

Comments:*Paule McGowan*

Paule McGowan



www.aaleastera.com

A&L Eastern Laboratories

7621 Whitepine Road Richmond, Virginia 23237 (804) 743-9401 Fax (804) 271-6446


TEXTURE ANALYSIS

Client : ENVIRONMENTAL AGRONOMICS POB 120 QUANTICO, MD 21856	Grower : PRINCE WILLIAM COUNTY SERVICE AUTHORITY OCCOQUAN FOREST STP Farm:	Report No : 14-287-0655 Cust No : 25273 Date Printed : 10/20/2014 Page : 1 of 1 Submitted By : D L JARRETT Date Received : 10/14/2014
---	---	--

<u>Lab No</u>	<u>Field ID</u>	<u>Sample Identification</u>	<u>Percent Sand</u>	<u>Percent Silt</u>	<u>Percent Clay</u>	<u>Textural Classification</u>
24494		SF-1 N SURFACE	46.0	38.0	16.0	Loam
24495		SF-1 N SUBSURFACE	36.0	36.0	28.0	Clay Loam
24496		SF-2 MID SURFACE	44.0	38.0	18.0	Loam
24497		SF-2 MID SUBSURFACE	38.0	32.0	30.0	Clay Loam
24498		SF-3 S SURFACE	44.0	42.0	14.0	Loam
24499		SF-3 S SUBSURFACE	40.0	32.0	28.0	Clay Loam

ATTACHMENT 9

PART D-1, ITEMS 18 AND 19
CROP AND SITE MANAGEMENT



Occoquan Forest STP

Agronomic Practices

This Land Treatment System was developed over twenty (20) years ago for the utilization of municipal wastewater in a forest ecosystem. The site was developed on very deep and deep well drained and somewhat excessively drained soils that have a clayey or loamy subsoil. The system is on medium-wide to narrow ridge tops with an erosion control structure built on the side slopes to prevent any runoff of the sprayed wastewater. A reverse bench structure or drainage ditch surrounding the spray fields protects the entire site. This forest system contains primarily mixed hardwood species with a large percentage of the area containing understory, which breaks the impact of the sprayed wastewater reducing the potential for runoff or erosion. The wastewater is being used in this system for irrigating the hardwood species as well as supplying nutrients (N-P-K) to increase their production. The current production of wastewater is providing approximately 50% of the required nutrients for maximum tree production. At this time, it is unlikely that any additional nutrients will be added to this spray site. The tree species will be cruised by a forester in the future for select harvesting the mature trees.